LMC Marymoor

17611 NE 70th Street

Redmond, Washington



Preliminary Stormwater Report

Site Plan Entitlement - Final Prep

Prepared by:
Jeremy Febus, PE
Kristin Ramey, EIT
KPFF Consulting Engineers
1601 Fifth Avenue, Suite 1600
Seattle, Washington 98101

KPFF Project No.1800077

February 2019





This Page Intentionally Left Blank

Preliminary Stormwater Report

February 2019

Prepared for:

City of Redmond 15670 NE 85th Street Redmond, WA 98052 (425) 556-2900

Prepared by:

Jeremy Febus, PE
Kristin Ramey, EIT
KPFF Consulting Engineers
1601 Fifth Avenue, Suite 1600
Seattle, WA 98101
(206) 622-5822
KPFF Project No. 1800077

Developer:

Lennar Multifamily Communities 1325 4th Avenue, Suite 1300 Seattle, WA 98101



February 2019

i

Table of Contents

1.	Project Overview	1
2.	Existing Conditions Summary	2
3.	Offsite Analysis Report	2
4.	MINIMUM Requirements MR NO. 1 – PREPARATION OF STORMWATER SITE PLANS	4 4 4 4 5
5.	Permanent Stormwater Control Plan EXISTING SITE HYDOLOGY Summary DEVELOPED SITE HYDROLOGY Summary Performance Standards and Goals Low Impact Development Features Flow Control System Water Quality System Conveyance System Analysis and Design	5 6 6 7 9
6.	Construction Stormwater Pollution Prevention Plan	10
7.	Special Reports and Studies	11
8.	Other Permits	
9.	Operations and Maintenance Manual	11

List of Figures

Figure 1 Vicinity Map	1
Figure 2 SWMMWW Figure 1-2.4.2, Annotated	3
Figure 3 SWMMWW Figure 1-2.5.1, Annotated	7
List of Tables	
Table 1 Existing Site Area	5
Table 2 Proposed Site Area	6
Table 3 SWMMWW LID List 2	8

Appendices

Appendix A

Existing Conditions

Proposed Conditions

Appendix B

Civil Utility Sheets

Appendix C

MGS Flood Reports

Appendix D

Geotechnical Report

This Page Intentionally Left Blank

1. Project Overview

This report analyzes storm drainage control measures for the proposed LMC Marymoor Multifamily Community. The project is subject to the Department of Ecology (Ecology) 2014 Stormwater Management Manual for Western Washington (SWMMWW), as amended by the City of Redmond (COR) Stormwater Technical Notebook.

The site is located at 17611 NE 70th Street in the City of Redmond, Washington. The parcel numbers for the site are 1225059229, 1225059095, and 1225059152. As shown in the Vicinity Map, Figure 1, the property is generally bounded by private properties on the south, 176th Avenue NE on the west, NE 70th Street on the north, and the East Lake Sammamish Trail to the east.

At approximately 5 acres with an existing impervious surface coverage in excess of 35%, the project is classified as a **Redevelopment** per the SWMMWW and as a **Large Project** per the Stormwater Technical Notebook. Previously zoned as an industrial site, the existing conditions consist of several small buildings, material stockpiles and storage areas, and parking for various classes of vehicles. Currently, all stormwater is infiltrated on site. Stormwater that lands in the right-of-way (ROW) adjacent to the project site either pools at a series of abandoned catch basins until it evaporates or it runs farther downstream until it reaches Marymoor Park.

The project proposes to construct a mixed used, multifamily residential building that includes ground floor commercial space and structured parking below grade. The project is a phased development that will be entitled under a Master Planned Development (MPD) permit and Site Plan Entitlement (SPE). Onsite stormwater will be treated using bioretention and routed to infiltration chambers outside the building footprint. ROW stormwater will be treated using a combination of bioretention planters and water quality treatment structures (Filterra or similar). Overflows from these facilities will be routed to infiltration drywells located under the sidewalk.



Figure 1: Vicinity Map

2. Existing Conditions Summary

The 5.0 acre project site is located in the Marymoor Design District. The present use is industrial. The site is generally flat and slopes gently towards the south property line. There, the grade drops steeply down to existing grade on the neighboring property.

The Marymoor Design District has a rudimentary storm system with no natural outfall and scattered disconnect segments of stormwater infrastructure. Currently, all onsite stormwater is infiltrated into the existing subgrade. ROW stormwater adjacent to the site is directed to catch basins that are either plugged or disconnected. There are no known off site areas that contribute stormwater to the site.

According to the project Geotechnical Report, most of the surficial soils on site consist of thin layers of gravel 6 to 12-inches thick. One exception to that appears to be at the southeast corner, which contain an isolated pocket of fill material. Beneath the surficial soils, the entire site is underlain by Qyal Younger Alluvium, which consists of layers of sand, silt and clay.

The majority of the Marymoor Design District is located in a Critical Aquifer Recharge Area (CARA), which is an Environmentally Critical Area (ECA) as defined by the City of Redmond (COR). The site is located in Wellhead Protection Zone 3, which has a five year travel time to City water supply wells. According to the project Geotechnical Report, groundwater levels in the alluvium subgrade vary seasonally from 29.7 to 37.6, which is due in part to fluctuations in precipitation and groundwater withdrawals at City well points.

For existing conditions, refer to the Existing Conditions figure in Appendix A.

3. Offsite Analysis Report

Per SWMMWW Volume 1, Chapter 1.6 and Section 2.6 of the Stormwater Technical Notebook, projects that discharge stormwater offsite are required to perform an offsite analysis. The site currently does not discharge stormwater offsite and no new discharge points are proposed. Therefore, an offsite analysis is not required or provided.

4. Minimum Requirements

Minimum requirements for redevelopment projects are outlined in Volume 1, Chapter 2, Figure 1-2.4.2 of the SWMMWW. Figure 1-2.4.2 is annotated below, indicating that this project exceeds the requirement thresholds for **Minimum Requirements 1-9**.

February 2019




Figure 2: SWMMWW Figure 1-2.4.2, Annotated

February 2019

MR NO. 1 - PREPARATION OF STORMWATER SITE PLANS

This report constitutes the preliminary project stormwater site plan as defined by Volume 1, Chapter 1-3.1 of the SWMMWW.

MR NO. 2 – CONSTRUCTION STORMWATER POLLUTION PREVENTION PLAN (SWPPP)

The project includes more than 2,000 square feet of new plus replaced hard surface area and will disturb more than 7,000 square feet of land disturbing activity. Therefore, per Section 2.5.2 of the Stormwater Technical Notebook the project must prepare a Construction SWPPP and Temporary Erosions and Sediment Control (TESC) plans. Refer to Section 6 of this report for a site specific discussion of construction stormwater pollution prevention requirements.

MR NO. 3 – SOURCE CONTROL OF POLLUTION

Per section 2.5.3 of the Stormwater Technical Notebook, all applicable and recommended source control BMPs as described in Volume 6 of the SWMMWW are required. Additional pollutant specific BMPs that may be required are:

- S411 BMPs for Landscaping and Lawn/ Vegetation Management
- S417 BMPs for Maintenance of Stormwater Drainage and Treatment Systems
- S424 BMPs for Roof/ Building Drains at Manufacturing and Commercial Buildings
- S433 BMPs for Pools, Spas, Hot Tubs, and Fountains

Required BMPs will be designed and documented as a part of the COR Coordinated Civil Review (CCR) process.

MR NO.4 - PRESERVATION OF NATURAL DRAINAGE SYSTEMS AND OUTFALLS

The site is comprised of a self contained on-site basin and an offsite ROW basin. Both basins rely on infiltration of stormwater. There are no downstream outfalls. The project matches existing drainage patterns by fully infiltrating project runoff.

MR NO. 5 - ON-SITE STORMWATER MANAGEMENT

Per Appendix B of the Stormwater Technical Notebook, the project is located within the Marymoor-100% Infiltration area. According to Section 2.5.5.2 of the Stormwater Technical Notebook, projects within this area do not need to demonstrate compliance with Minimum Requirement 5 because they will exceed the intent of Minimum Requirement 5 by infiltrating 100% of their runoff. Refer to the Low Impact Development discussion in Section 6 of this report for a description of how infiltration requirements are being met.

MR NO.6 - RUNOFF TREATMENT

Per Section 2.5.3 of the Stormwater Technical Notebook, the Marymoor Design District has highly infiltrative soils and is outside Wellhead Protection Zones that prohibit infiltration of runoff from pollution generating hard surfaces. However the proposed development is a mixed use commercial residential

project within a quarter mile of a fresh water body with an existing aquatic life use. Therefore, per SWMMWW Volume 5, Chapter 2.1, the project must meet the requirement of Enhanced Water Quality Treatment prior to infiltrating. Refer to the Water Quality System discussion in Section 5 of this report for a description of how water quality treatment requirements are being met.

MR NO.7 - FLOW CONTROL

Per Appendix D of the Stormwater Technical Notebook, the project must infiltrate 100% of site stormwater to meet flow control requirements. Refer to the Flow Control System discussion in Section 5 for a description of how flow control requirements are being met.

MR NO. 8 - WETLANDS PROTECTION

This site does not discharge to a wetland or its buffer and there are no wetlands in the vicinity, therefore wetland protection is not required.

MR NO. 9 - OPERATION AND MAINTENANCE MANUAL

An Operation and Maintenance Manual for the stormwater infrastructure will be provided through the CCR process.

5. Permanent Stormwater Control Plan

EXISTING SITE HYDOLOGY

Summary

The existing site surfaces are predominantly graveled, with few paved surfaces and roofs to generate significant storm runoff. Though gravel is not considered softscape, it provides substantial depression storage, allowing water to pool and infiltrate into the underlying alluvium. Refer to Table 1 and the Existing Conditions Exhibit in Appendix A for existing surface areas.

Table 1: Existing Surface Areas

Land Cover	Total Area
ROW Paved PGIS	0.39 acres
Onsite Paved PGIS	1.41 acres
Gravel PGIS	3.24 acres
Roof NGIS	0.40 acres
Total	5.43 acres

DEVELOPED SITE HYDROLOGY

Summary

The proposed hydrology approximately matches existing right of way and on-site basins. In addition, impervious area coverage is reduced through the addition of streetscape planting and on-site landscape improvements. Further, the proposed conditions improve upon existing on-site and ROW hydrology by providing a control means of infiltration through the use of infiltration chambers and drywells. Refer to Table 2 and the Proposed Conditions Exhibit in Appendix A for proposed surface areas.

Table 2: Proposed Surface Areas

Land Cover	Total Area
ROW PGIS	0.75 acres
ROW NPGIS	0.43 acres
ROW Pervious	0.14 acres
Onsite PGIS	0.14 acres
Onsite NPGIS	1.06 acres
Onsite Roof	2.26 acres
Onsite Pervious	0.63 acres
Pools	0.02 acres
Total	5.43 acres

Performance Standards and Goals

Per the SWMMWW and the Stormwater Technical Notebook, the following performance standards and goals apply to this project:

- Runoff Generation
 - o MGS Flood continuous modeling software was used to generate runoff for LID, flow control, and water quality calculations. The assumptions for the model are as follows:
 - Puget 40 East Time Series
 - 5 minute computational time step
 - Hard surfaces modeled as impervious
 - Landscape areas modeled as till-grass
- LID and Flow Control
 - o 100% Infiltration
- Water Quality
 - o Enhanced Water Quality

Low Impact Development Features

Site Assessment

Per Section 8.7.5 of the Stormwater Technical Notebook, all projects that trigger Minimum Requirement 1 are required to include a LID Site Assessment as a part of the stormwater site plan. The following documents, required for the LID Site Assessment, are included with this report or under separate cover:

- Survey meeting all the requirements of Volume 1, Chapter 3.1 of SWMMWW (included as a base in the exhibits in Appendix A and in the plan set included with this submittal).
- Geotechnical reports (refer to the Special Report and Studies discussion in Section 7 of this report)

The following documents are not included in this report:

- Critical Areas Report: The project is located in Wellhead Protection Zone 3.
- Flood Hazard Report: This site is not located in a flood plain.

LID Requirements

The process for determining minimum LID requirements is outlined in SWMMWW Volume 1, Chapter 2, Figure 1-2.5.1. This figure is annotated below, indicating that this project is required to evaluate BMPs for proposed surfaces using the BMP hierarchy outlined in List #2. Refer to Table 3 for the BMP list.




Figure 3: SWMMWW Figure 1-2.5.1, Annotated

Table 3: SWMMWW LID List 2

LIST #2: ON-SITE STORMWATER MANAGEMENT BMPS						
List Order Hierarchy	Required BMP					
Lawn and Landscape Are	eas					
1	Post-Construction Soil Quality and Depth					
Roofs						
1	Full Dispersion or Downspout Full Infiltration					
2 Bioretention						
3	Downspout Dispersion					
4	Perforated Stub-out Connections					
Other Hard Surfaces						
1	Full Dispersion					
2	Permeable Pavement					
3	Bioretention					
4	Sheet Flow Dispersion or Concentrated Flow Dispersion					

Feasibility and Implementation

The feasibility study of List #2 BMPs included added considerations to account for the full infiltration requirements outlined in Section 2.5.5.2 and Appendix B of the Stormwater Technical Notebook. The project evaluated horizontal setbacks from buildings, structures, storage tanks, and property lines. In addition, the project considered vertical setbacks from seasonal high water and any highly variable or hydraulically restrictive soil zones that may impact infiltration capabilities described in the project Geotechnical Report.

According to the Geotechnical Report, the site soils have a measured infiltration capacity of 85 inches per hour. This value exceeds the maximum allowable design infiltration rate of 20 inches per hour indicated in Section 2.9.3.9 of the Stormwater Technical Notebook, therefore a long term design infiltrations rate of 20 inches per hour was used in calculations. The Geotechnical Report also includes updated information on groundwater elevations, recommending a design seasonal high groundwater elevation of 37.6 feet. All infiltrating facilities are required to maintain at least three feet of separation from the seasonal high groundwater level. In addition, mounding analyses are required for all facilities situated less than 5 feet above the seasonal high groundwater elevation.

The additional infiltration criteria narrowed the feasible BMPs in List #2 down to infiltrating BMPs only. From this limited list, the project proposes to implement soil amendments for the restoration of all offstructure landscape areas to meet the requirements for post-construction soil quality and depth. In addition, the project proposes to manage all roof surfaces onsite using infiltrating BMPs to meet requirement for downspout full infiltration. The project also proposes to employ bioretention in conjunction with other infiltrating BMPs to manage other hard surfaces onsite and in the ROW

On-Site Stormwater Management

Onsite stormwater will be managed though the use of downspout full infiltration. The stormwater will be routed to infiltration chambers at the southeast corner of the property. Preliminary modeling results indicate that an estimated infiltration chamber system volume of 8,504 cubic feet would be required to infiltrate 100% of onsite stormwater. Refer to the Proposed Conditions Exhibit in Appendix A for onsite basins and to Appendix C for preliminary modeling results.

The project is currently proposing an infiltration chamber system that provides approximately 9,000 cubic feet of storage, covering approximately 4,500 square feet. The bottom of the facility is situated five feet above the seasonally high groundwater elevation as documented in the project Geotechnical Report, rendering a mounding analysis unnecessary at this time. As the onsite stormwater design progresses, the facility configuration and elevations may change. If the groundwater separation decreases as the design develops, a mounding analysis will be performed on the infiltration chambers to confirm that the system will have no adverse impacts to the groundwater table or adjacent structures. Refer to the Civil Utility Sheets in Appendix B for the preliminary facility location, as well as documentation of horizontal and vertical setbacks.

Right of Way Stormwater Management

ROW stormwater will be managed though the use of infiltrating bioretention, drywells, and infiltration chambers. Stormwater will be routed to bioretention facilities and water quality treatment structures (Filterra or similar) situated in the ROW. Bioretention facilities will be used for both water quality treatment and infiltration of stormwater, while water quality structures will only be used for treatment. Underdrains and overflows from bioretention facilities and outlets from water quality treatment structures will be routed drywells and infiltration chambers. The bottom of these infiltrating facilities will be situated at least three feet above the seasonal high groundwater level.

The project is currently proposing a ROW drainage system comprised of seven dedicated infiltrating facilities served by separate stormwater basins. These facilities and their basins may be reconfigured, combined, or divided as the stormwater design progresses. Refer to the Proposed Conditions Exhibit in Appendix A for ROW basins, to the Civil Utility Sheets in Appendix B for preliminary facility locations, and to Appendix C for preliminary modeling results.

Flow Control System

The Marymoor Design District has little-to-no conveyance infrastructure and no stormwater outfalls. Therefore, as indicated in Appendix D of the Stormwater Technical Notebook, the project will be required to infiltrate 100% of stormwater to meet flow control requirements. This will result in a net-zero offsite flow, preventing erosion of downstream properties. Refer to the Low Impact Development Section of this report for a discussion of the infiltration design.

Water Quality System

Per SWMMWW Volume 5, Chapter 2.1, the project is required to provide Enhanced Water Quality Treatment prior to infiltrating stormwater. Enhanced treatment BMPs are outlined in SWMMWW Volume 5, Chapter 3.4. Given the industrial nature of the surrounding area and the confined spaced available for siting water quality facilities, applicable stormwater treatment BMPs are limited to bioretention facilities and approved emerging technologies (i.e. Filterra or similar). The project will implement bioretention and water quality treatment structures in the ROW to provide treatment prior to being sent to the infiltration drywells. Onsite, runoff from pollution generating surfaces will be routed though bioretention facilities before the sent to the infiltration chambers. Refer to the Low Impact Development section of this report for a discussion of the onsite and ROW infiltration design.

Conveyance System Analysis and Design

The proposed onsite drainage system is minimal. The majority of the site is over the garage structure, which means that drainage picked up on site will be routed through internal plumbing. The point of

connection for the onsite storm system is at the southeast corner of the building. From there, the stormwater is routed a short distance via a 18-inch storm line to the proposed infiltration chambers off structure. Refer to the Low Impact Development section of this report for a discussion of the onsite infiltration design.

The ROW drainage system consists of a series of bioretention facilities and water quality treatment structures routed to infiltration drywells. Roadway and sidewalk grading is used to route stormwater to the inlets of the bioretention and water quality facilities. From there, underdrains and overflows from the bioretention and outlets from the water quality treatment structures are routed to infiltration facilities. Refer to the Low Impact Development section of this report for a discussion of the ROW infiltration design.

Pipe sizes and layout were selected based on required full flow capacities and minimum slopes necessary to achieve 3 feet per second full flow velocity. These design parameters represent the baseline assumptions used to layout the conveyance system. In instances site constraints impacted baseline design, conveyance elements were analyzed on a case by case basis. A uniform flow analysis of the proposed conveyance system as described in the 2016 King County Surface Water Design Manual will be performed as a part of the CCR process. Backwater analyses will not be necessary as there are no downstream systems that could impact hydraulic grades lines.

Construction Stormwater Pollution Prevention Plan

This project will require coverage under Ecology Construction Stormwater General Permit because the total disturbed area is greater than 1 acre. The NOI will be prepared and submitted to Ecology, and SWPPP approval will be received from the City prior to any land-disturbing activities. The SWPPP and accompanying TESC plan sheets for this project will be prepared as a part of the CCR process. The design will implement adequately sized best management practices (BMPs) to meet construction stormwater pollution prevention requirements. These BMPs will include the following elements:

- 1. Mark Clearing Limits and Environmentally Critical Areas (ECAs).
- 2. Retain Top Layer.
- 3. Establish Construction Access.
- 4. Protect Downstream Properties and Receiving Waters.
- 5. Prevent Erosion and Sediment Transport from Site.
- 6. Prevent Erosion and Sediment Transport from Site by Vehicles.
- 7. Stabilize Soils.
- 8. Protect Slopes.
- 9. Protect Storm Drains.
- 10. Stabilize Channels and Outlets.
- 11. Control Pollutants, including sediment, waste, chemicals, petroleum products, fertilizers, pesticides, and runoff affected by pH-modifying activities.
- 12. Control Dewatering, including flow rates and quality.
- 13. Maintain BMPs.

February 2019

- 14. Inspect BMPs.
- 15. Execute and Update Construction Stormwater and Erosion Control Plan.
- 16. Minimize Open Trenches.
- 17. Phase the Project.
- 18. Install Flow Control and Water Quality Facilities.
- 19. Protect Stormwater BMPs.

7. Special Reports and Studies

The following reports are included under a separate cover as a part of this submittal:

"Geotechnical Report, LMC Marymoor, 17611 Northeast 70th Street, Redmond, Washington" *PanGEO, Inc*, August, 2018.

8. Other Permits

There are no other permits associated with the LMC Marymoor Project at this time.

9. Operations and Maintenance Manual


An Operations and Maintenance Manual will be prepared for this site and will be included in the Final report to be submitted as part of the COR Coordinated Civil Review.


This Page Intentionally Left Blank

Appendix A

- 1. Existing Conditions
- 2. Proposed Conditions

This Page Intentionally Left Blank






Appendix B

1. Civil Utility Sheets

This Page Intentionally Left Blank



DESIGNED BY PREP ROUND 1 JSF JSF CALL TWO BUSINESS DAYS BEFORE YOU DIG 1-800-424-5555 JEP/RG KFR 10/18/18 JSF PREP ROUND 2 CHECKED BY APPROVED B 12/21/18 PREP ROUND 3 JSF JSF JSF DATE 01/14/19 JSF DD PRICING SET JSF 02/28/2019 100% PREP SET JSF JSF J O B No. :1800077 CHD. APPR. REVISION BY DATE

S C A L E:

AS NOTED



LMC MARYMOOR SHEET REDMOND, WA

UTILITIES & DRAINAGE PLAN

|C-2.00|

PROPOSED PROPERTY LINE

CENTERLINE

——sd———— STORM LINE

FIRE SERVICE LINE

FILTERRA STRUCTURES

AREA DRAIN

CLEANOUT

DRYWELL/SDMH

SSMH

→ HYDRANT

FDC

AIR RELIEF VALVE

→ WATER FITTINGS


POST INDICATOR VALVE

■ WATER METER

810 LA VAULT

NOTES:

- 1. UTILITY LOCATES SHALL BE PERFORMED TO DETERMINE VERTICAL CLEARANCES BETWEEN EXISTING AND PROPOSED UTILITIES AND TO IDENTIFY POSSIBLE UTILITY CONFLICTS PRIOR TO CCR APPROVAL.
- 2. REFER TO C-4.00 FOR ONSITE AND OFFSITE BASIN AREAS.
- 3. SEWER MAIN IN 176TH AVENUE NE WILL BE UPSIZED TO 10" BY COR AS A PART OF REGIONAL PUMP STATION IMPROVEMENTS. NEW SEWER MAIN WILL EITHER MAINTAIN EXISTING IE'S OR DEEPEN THEM. PROJECT WILL COORDINATE WITH COR'S CONTRACTOR TO DETERMINE FINAL PIPE AND STRUCTURE INVERTS.
- 4.) ROW UTILITIES IN HARDSCAPE SHALL HAVE NON-SKID LID.



NE 70TH STREET PROFILE

SCALE: H: 1" = 20' V: 1" = 5'

51+60

EXIST 8" PVC SEWER

52+00

DESIGNED BY 8/13/18 PREP ROUND 1 JSF JSF CALL TWO BUSINESS JEP/RG KFR 10/18/18 JSF PREP ROUND 2 JSF CHECKED BY APPROVED BY DAYS BEFORE YOU DIG 12/21/18 PREP ROUND 3 JSF JSF JSF JSF 1-800-424-5555 01/14/19 DATE JSF JSF DD PRICING SET KFR 02/28/2019 02/28/19 100% PREP SET JSF KFR JSF S C A L E: J O B No. :1800077 AS NOTED CHD. APPR. REVISION BY NO. DATE

35

50+80

51+20





52+80

53+20


52+40


UTILITIES & DRAINAGE PLAN & PROFILE

LMC MARYMOOR

REDMOND, WA

C-2.01





EXISTING PROPERTY LINE
PROPOSED PROPERTY LINE
CENTERLINE
STORM LINE
SEWER LINE
WATER LINE
FIRE SERVICE LINE
FILTERRA STRUCTURES
AREA DRAIN
CLEANOUT
DRYWELL/SDMH
SSMH
HYDRANT
FDC
AIR RELIEF VALVE
WATER FITTINGS
POST INDICATOR VALVE
WATER METER
810 LA VAULT

NOTES:

- 1. UTILITY LOCATES SHALL BE PERFORMED TO DETERMINE VERTICAL CLEARANCES BETWEEN EXISTING AND PROPOSED UTILITIES AND TO IDENTIFY POSSIBLE UTILITY CONFLICTS PRIOR TO CCR APPROVAL.
- 2. REFER TO C-4.00 FOR ONSITE AND OFFSITE BASIN AREAS.
- 3.) SEWER MAIN IN 176TH AVENUE NE WILL BE UPSIZED TO 10" BY COR AS A PART OF REGIONAL PUMP STATION IMPROVEMENTS. NEW SEWER MAIN WILL EITHER MAINTAIN EXISTING IE'S OR DEEPEN THEM. PROJECT WILL COORDINATE WITH COR'S CONTRACTOR TO DETERMINE FINAL PIPE AND STRUCTURE INVERTS.
- (4.) ROW UTILITIES IN HARDSCAPE SHALL HAVE NON-SKID LID.

1	8/13/18	KFR	JSF	JSF	PREP ROUND 1	DRAWN BY	DESIGNED BY	CALL TWO DUCINECS
2	10/18/18	KFR	JSF	JSF	PREP ROUND 2	JEP/RG CHECKED BY	KFR APPROVED BY	CALL TWO BUSINESS
3	12/21/18	KFR	JSF	JSF	PREP ROUND 3	JSF	JSF	DAIS DLIVINE IVU DIU
4	01/14/19	KFR	JSF	JSF	DD PRICING SET	DA		1-800-424-5555
5	02/28/19	KFR	JSF	JSF	100% PREP SET	02/28	/2019	SCALE:
NO.	DATE	BY	CHD.	APPR.	REVISION	JOB No.	:1800077	AS NOTED



176TH AVENUE NE PROFILE


SCALE: H: 1" = 20' V: 1" = 5'



LMC MARYMOOR REDMOND, WA

SHEET

C-2.02



LEGEND:

EXISTING PROPERTY LINE

PROPOSED PROPERTY LINE

— — CENTERLINE

—SD——— STORM LINE

——ss——— SEWER LINE

----- WATER LINE

— FIRE SERVICE LINE

FILTERRA STRUCTURES

AREA DRAIN

CLEANOUT

DRYWELL/SDMH

) SSMH

FDC

AIR RELIEF VALVE

⇒ WATER FITTINGS

POST INDICATOR VALVE

■ WATER METER

242 14 14

810 LA VAULT


NOTES:

- 1. UTILITY LOCATES SHALL BE PERFORMED TO DETERMINE VERTICAL CLEARANCES BETWEEN EXISTING AND PROPOSED UTILITIES AND TO IDENTIFY POSSIBLE UTILITY CONFLICTS PRIOR TO CCR APPROVAL.
- 2. REFER TO C-4.00 FOR ONSITE AND OFFSITE BASIN AREAS.
- 3.) SEWER MAIN IN 176TH AVENUE NE WILL BE UPSIZED TO 10" BY COR AS A PART OF REGIONAL PUMP STATION IMPROVEMENTS. NEW SEWER MAIN WILL EITHER MAINTAIN EXISTING IE'S OR DEEPEN THEM. PROJECT WILL COORDINATE WITH COR'S CONTRACTOR TO DETERMINE FINAL PIPE AND STRUCTURE INVERTS.
- 4.) ROW UTILITIES IN HARDSCAPE SHALL HAVE NON-SKID LID.

1	8/13/18	KFR	JSF	JSF	PREP ROUND 1		DESIGNED BY	CALL TWO BUSINESS
2	10/18/18	KFR	JSF	JSF	PREP ROUND 2			
3	12/21/18	KFR	JSF	JSF	PREP ROUND 3	JSF	JSF	
4	01/14/19	KFR	JSF	JSF	DD PRICING SET			1-800-424-5555
5	02/28/19	KFR	JSF	JSF	100% PREP SET	, , , , , , , , , , , , , , , , , , ,	•	S C A L E:
NO.	DATE	BY	CHD.	APPR.	REVISION	JOB No.	:1800077	AS NOTED
	1 2 3 4 5 NO.	2 10/18/18 3 12/21/18 4 01/14/19 5 02/28/19	2 10/18/18 KFR 3 12/21/18 KFR 4 01/14/19 KFR 5 02/28/19 KFR	2 10/18/18 KFR JSF 3 12/21/18 KFR JSF 4 01/14/19 KFR JSF 5 02/28/19 KFR JSF	2 10/18/18 KFR JSF JSF 3 12/21/18 KFR JSF JSF 4 01/14/19 KFR JSF JSF 5 02/28/19 KFR JSF JSF	2 10/18/18 KFR JSF JSF PREP ROUND 2 3 12/21/18 KFR JSF JSF PREP ROUND 3 4 01/14/19 KFR JSF JSF DD PRICING SET 5 02/28/19 KFR JSF JSF 100% PREP SET	2 10/18/18 KFR JSF JSF PREP ROUND 2 JEP/RG CHECKED BY SF 3 12/21/18 KFR JSF JSF PREP ROUND 3 JSF 4 01/14/19 KFR JSF JSF DD PRICING SET DA O2/28 5 02/28/19 KFR JSF JSF 100% PREP SET LORANGE	2 10/18/18 KFR JSF JSF PREP ROUND 2 3 12/21/18 KFR JSF JSF PREP ROUND 3 4 01/14/19 KFR JSF JSF DD PRICING SET 5 02/28/19 KFR JSF JSF 100% PREP SET



SCALE: H: 1" = 20' V: 1" = 5'




UTILITIES & DRAINAGE PLAN & PROFILE

LMC MARYMOOR

REDMOND, WA

2-2.03




LEGEND:	
	EXISTING PROPERTY LINE
	PROPOSED PROPERTY LINE
	CENTERLINE
sp	STORM LINE
ss	SEWER LINE
w	WATER LINE
FS	FIRE SERVICE LINE
	FILTERRA STRUCTURES
	AREA DRAIN
•	CLEANOUT
	DRYWELL/SDMH
	SSMH
.	HYDRANT
•	FDC
A °	AIR RELIEF VALVE
; ₩	WATER FITTINGS
Å	POST INDICATOR VALVE
28	WATER METER
	810 LA VAULT
=	

NOTES:

- 1. UTILITY LOCATES SHALL BE PERFORMED TO DETERMINE VERTICAL CLEARANCES BETWEEN EXISTING AND PROPOSED UTILITIES AND TO IDENTIFY POSSIBLE UTILITY CONFLICTS PRIOR TO CCR APPROVAL.
- 2. REFER TO C-4.00 FOR ONSITE AND OFFSITE BASIN AREAS.
- 3. SEWER MAIN IN 176TH AVENUE NE WILL BE UPSIZED TO 10" BY COR AS A PART OF REGIONAL PUMP STATION IMPROVEMENTS. NEW SEWER MAIN WILL EITHER MAINTAIN EXISTING IE'S OR DEEPEN THEM. PROJECT WILL COORDINATE WITH COR'S CONTRACTOR TO DETERMINE FINAL PIPE AND STRUCTURE INVERTS.
- 4.) ROW UTILITIES IN HARDSCAPE SHALL HAVE NON-SKID LID.

9 – 3:34pm	1 8/13/18 KFR JSF JSF PREP ROUN 2 10/18/18 KFR JSF JSF PREP ROUN	JEP/RG KFR CHECKED BY APPROVED B	CALL TWO BUSINESS DAYS BFFORF YOU DIG	S. WASHING DE	LMC MARYMOOR REDMOND, WA	SHEET
eb 27, 2019	3 12/21/18 KFR JSF JSF PREP ROUN 4 01/14/19 KFR JSF JSF DD PRICING	DATE 02/28/2019	1-800-424-5555 Seattle, WA 98101 206.622.5822 www.kpff.com	39847	UTILITIES & DRAINAGE PLAN & PROFILE	C-2.04
	5 02/28/19 KFR JSF JSF 100% PREP NO. DATE BY CHD. APPR.	REVISION J 0 B No. :1800077	S C A L E: AS NOTED	SSIONAL ENGLISH		



LEGEND:	
	- EXISTING PROPERT

EXISTING PROPERTY LINE

---- PROPOSED PROPERTY LINE

— — CENTERLINE

——SD———— STORM LINE

—ss—— SEWER LINE

—FS——— FIRE SERVICE LINE

FILTERRA STRUCTURES

AREA DRAIN

CLEANOUT

DRYWELL/SDMH

SSMH

◆ FDC

♣ AIR RELIEF VALVE

HYDRANT

¥ WATER FITTINGS

POST INDICATOR VALVE

■ WATER METER

810 LA VAULT

NOTES:

- 1. UTILITY LOCATES SHALL BE PERFORMED TO DETERMINE VERTICAL CLEARANCES BETWEEN EXISTING AND PROPOSED UTILITIES AND TO IDENTIFY POSSIBLE UTILITY CONFLICTS PRIOR TO CCR APPROVAL.
- 2. REFER TO C-4.00 FOR ONSITE AND OFFSITE BASIN AREAS.
- 3. SEWER MAIN IN 176TH AVENUE NE WILL BE UPSIZED TO 10" BY COR AS A PART OF REGIONAL PUMP STATION IMPROVEMENTS. NEW SEWER MAIN WILL EITHER MAINTAIN EXISTING IE'S OR DEEPEN THEM. PROJECT WILL COORDINATE WITH COR'S CONTRACTOR TO DETERMINE FINAL PIPE AND STRUCTURE INVERTS.
- 4.) ROW UTILITIES IN HARDSCAPE SHALL HAVE NON-SKID LID.

md7.7	1	8/13/18	KFR	JSF	JSF	PREP ROUND 1	DRAWN BY	DESIGNED BY	CALL TWO DISCINICO
- 2:2	2	10/18/18	KFR	JSF	JSF	PREP ROUND 2	JEP/RG CHECKED BY	KFR APPROVED BY	CALL TWO BUSINESS
2019	3	12/21/18	KFR	JSF	JSF	PREP ROUND 3	JSF	JSF	I NAIS DELVIVE TOO DID I
27,	4	01/14/19	KFR	JSF	JSF	DD PRICING SET		ATE (2010	1-800-424-5555
r eb	5	02/28/19	KFR	JSF	JSF	100% PREP SET	<u> </u>	/2019	SCALE:
	NO.	DATE	BY	CHD.	APPR.	REVISION	JOB No.	:1800077	AS NOTED





UTILITIES & DRAINAGE PLAN & PROFILE

REDMOND, WA

C-2.05

EXISTING PROPERTY LINE

---- PROPOSED PROPERTY LINE

FILTERRA STRUCTURES

---- CENTERLINE

STORM LINE

— SEWER LINE --- WATER LINE

— FIRE SERVICE LINE

AREA DRAIN

CLEANOUT

DRYWELL/SDMH

HYDRANT

FDC

AIR RELIEF VALVE

₩ WATER FITTINGS


POST INDICATOR VALVE


WATER METER

810 LA VAULT

NOTES:

- 1. UTILITY LOCATES SHALL BE PERFORMED TO DETERMINE VERTICAL CLEARANCES BETWEEN EXISTING AND PROPOSED UTILITIES AND TO IDENTIFY POSSIBLE UTILITY CONFLICTS PRIOR TO CCR APPROVAL.
- 2. REFER TO C-4.00 FOR ONSITE AND OFFSITE BASIN AREAS.
- 3.) SEWER MAIN IN 176TH AVENUE NE WILL BE UPSIZED TO 10" BY COR AS A PART OF REGIONAL PUMP STATION IMPROVEMENTS. NEW SEWER MAIN WILL EITHER MAINTAIN EXISTING IE'S OR DEEPEN THEM. PROJECT WILL COORDINATE WITH COR'S CONTRACTOR TO DETERMINE FINAL PIPE AND STRUCTURE INVERTS.
- (4.) ROW UTILITIES IN HARDSCAPE SHALL HAVE NON-SKID LID.





NE 69TH STREET PROFILE SCALE: H: 1" = 20' V: 1" = 5'


2: 22pm	1	8/13/18	KFR	JSF	JSF	PREP ROUND 1	DRAWN BY	DESIGNED BY	CALL TWO DUCINIFCS
- 2:2	2	10/18/18	KFR	JSF	JSF	PREP ROUND 2	JEP/RG CHECKED BY	KFR APPROVED BY	CALL TWO BUSINESS DAYS BEFORE YOU DIG
2019	3	12/21/18	KFR	JSF	JSF	PREP ROUND 3	JSF	JSF	
27,	4	01/14/19	KFR	JSF	JSF	DD PRICING SET		ATE (2010	1-800-424-5555
Feb	5	02/28/19	KFR	JSF	JSF	100% PREP SET	<u> </u>	/2019	SCALE:
	NO.	DATE	BY	CHD.	APPR.	REVISION	JOB No.	:1800077	AS NOTED





LMC MARYMOOR

REDMOND, WA



LEGEND:	
	EXISTING PROPERTY LINE
	PROPOSED PROPERTY LI
	CENTERLINE
sD	STORM LINE
ss	SEWER LINE
——w——	WATER LINE
FS	FIRE SERVICE LINE
	FILTERRA STRUCTURES
	AREA DRAIN
•	CLEANOUT
	DRYWELL/SDMH
	SSMH
-	HYDRANT
•	FDC
*	AIR RELIEF VALVE
¼ : ₩	WATER FITTINGS
*	POST INDICATOR VALVE
	WATER METER
	810 LA VAULT

NOTES:

- 1. UTILITY LOCATES SHALL BE PERFORMED TO DETERMINE VERTICAL CLEARANCES BETWEEN EXISTING AND PROPOSED UTILITIES AND TO IDENTIFY POSSIBLE UTILITY CONFLICTS PRIOR TO CCR APPROVAL.
- 2. REFER TO C-4.00 FOR ONSITE AND OFFSITE BASIN AREAS.
- 3.) SEWER MAIN IN 176TH AVENUE NE WILL BE UPSIZED TO 10" BY COR AS A PART OF REGIONAL PUMP STATION IMPROVEMENTS. NEW SEWER MAIN WILL EITHER MAINTAIN EXISTING IE'S OR DEEPEN THEM. PROJECT WILL COORDINATE WITH COR'S CONTRACTOR TO DETERMINE FINAL PIPE AND STRUCTURE INVERTS.
- (4.) ROW UTILITIES IN HARDSCAPE SHALL HAVE NON-SKID LID.

– 2:22pm	2	10/18/18	KFR	JSF	JSF	PREP ROUND 2	JEP/RG CHECKED BY	KFR APPROVED BY	CALL DAYS
2019	3	12/21/18	KFR	JSF	JSF	PREP ROUND 3	JSF	JSF	II 4 6
, 27,	4	01/14/19	KFR	JSF	JSF	DD PRICING SET		ATE R (2010	
Feb	5	02/28/19	KFR	JSF	JSF	100% PREP SET	02/28	3/2019	S
	NO.	DATE	BY	CHD.	APPR.	REVISION	J O B No.	. :1800077	 A

L TWO BUSINESS YS BEFORE YOU DIG 1-800-424-5555 S C A L E: AS NOTED


SCALE: H: 1" = 20' V: 1" = 5'





LMC MARYMOOR

REDMOND, WA



LEGEND: EXISTING PROPERTY LINE - --- PROPOSED PROPERTY LINE ---- CENTERLINE — STORM LINE SEWER LINE ---- WATER LINE -FS FIRE SERVICE LINE FILTERRA STRUCTURES AREA DRAIN CLEANOUT DRYWELL/SDMH SSMH HYDRANT FDC AIR RELIEF VALVE **₩** WATER FITTINGS POST INDICATOR VALVE WATER METER

NOTES:

1. UTILITY LOCATES SHALL BE PERFORMED TO DETERMINE VERTICAL CLEARANCES BETWEEN EXISTING AND PROPOSED UTILITIES AND TO IDENTIFY POSSIBLE UTILITY CONFLICTS PRIOR TO CCR APPROVAL.

810 LA VAULT


- 2. REFER TO C-4.00 FOR ONSITE AND OFFSITE BASIN AREAS.
- 3. SEWER MAIN IN 176TH AVENUE NE WILL BE UPSIZED TO 10" BY COR AS A PART OF REGIONAL PUMP STATION IMPROVEMENTS. NEW SEWER MAIN WILL EITHER MAINTAIN EXISTING IE'S OR DEEPEN THEM. PROJECT WILL COORDINATE WITH COR'S CONTRACTOR TO DETERMINE FINAL PIPE AND STRUCTURE INVERTS.
- 4.) ROW UTILITIES IN HARDSCAPE SHALL HAVE NON-SKID LID.

ONSITE PROFILE

SCALE: H: 1" = 20' V: 1" = 5'

Ī	1	8/13/18	KFR	JSF	JSF	PREP ROUND 1	DRAWN BY	DESIGNED BY	CALL TWO DUCINECE
	2	10/18/18	KFR	JSF	JSF	PREP ROUND 2	JEP/RG CHECKED BY	KFR APPROVED BY	CALL TWO BUSINESS DAYS BEFORE YOU DIG
	3	12/21/18	KFR	JSF	JSF	PREP ROUND 3	JSF	JSF	ן טוע טטו ווער וער ווער און און און
	4	01/14/19	KFR	JSF	JSF	DD PRICING SET		ATE VOCAC	1-800-424-5555
	5	02/28/19	KFR	JSF	JSF	100% PREP SET	02/28	3/2019	SCALE:
	NO.	DATE	BY	CHD.	APPR.	REVISION	JOB No.	:1800077	AS NOTED






SEE SHEET C-2.05
MATCHLINE:

LMC MARYMOOR

REDMOND, WA

2-2.08




SC-740 INFILTRATION CHAMBER



2: 23pm	1	8/13/18	KFR	JSF	JSF	PREP ROUND 1		DRAWN BY	DESIGNED BY	CALL
- 2:2	2	10/18/18	KFR	JSF	JSF	PREP ROUND 2		JEP/RG CHECKED BY	KFR APPROVED BY	CALL
2019	3	12/21/18	KFR	JSF	JSF	PREP ROUND 3		JSF	JSF	DAYS
27,	4	01/14/19	KFR	JSF	JSF	DD PRICING SET		DA		
Feb	5	02/28/19	KFR	JSF	JSF	100% PREP SET		02/28	/2019	S
	NO.	DATE	BY	CHD.	APPR.		REVISION	JOB No.	:1800077	ļ







LMC	MARYMOOR	
RE	DMOND, WA	

SHEET




LMC MARYMOOR

ACCEPTABLE FILL MATERIALS: STORMTECH SC-310 CHAMBER SYSTEMS COMPACTION / DENSITY AASHTO MATERIAL MATERIAL LOCATION DESCRIPTION CLASSIFICATIONS REQUIREMENT FINAL FILL: FILL MATERIAL FOR LAYER 'D' STARTS FROM THE TOP OF THE 'C' LAYER TO THE BOTTOM ANY SOIL/ROCK MATERIALS, NATIVE SOILS, OR PER PREPARE PER SITE DESIGN ENGINEER'S PLANS. ENGINEER'S PLANS. CHECK PLANS FOR PAVEMENT OF FLEXIBLE PAVEMENT OR UNPAVED FINISHED PAVED INSTALLATIONS MAY HAVE STRINGENT GRADE ABOVE. NOTE THAT PAVEMENT SUBBASE SUBGRADE REQUIREMENTS. MATERIAL AND PREPARATION REQUIREMENTS. MAY BE PART OF THE 'D' LAYER BEGIN COMPACTIONS AFTER 12" (300 mm) OF AASHTO M1451 MATERIAL OVER THE CHAMBERS IS REACHED. A-1, A-2-4, A-3 COMPACT ADDITIONAL LAYERS IN 6" (150 mm) MAX INITIAL FILL: FILL MATERIAL FOR LAYER 'C' GRANULAR WELL-GRADED SOIL/AGGREGATE MIXTURES, <35% LIFTS TO A MIN. 95% PROCTOR DENSITY FOR STARTS FROM THE TOP OF THE EMBEDMENT FINES OR PROCESSED AGGREGATE. WELL GRADED MATERIAL AND 95% RELATIVE STONE ('B' LAYER) TO 18" (450 mm) ABOVE THE DENSITY FOR PROCESSED AGGREGATE MOST PAVEMENT SUBBASE MATERIALS CAN BE USED IN LIEU TOP OF THE CHAMBER. NOTE THAT PAVEMENT AASHTO M431 SUBBASE MAY BE A PART OF THE 'C' LAYER. MATERIALS. ROLLER GROSS VEHICLE WEIGHT OF THIS LAYER. , 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 89 NOT TO EXCEED 12,000 lbs (53 kN). DYNAMIC 9, 10 FORCE NOT TO EXCEED 20,000 lbs (89 kN). EMBEDMENT STONE: FILL SURROUNDING THE AASHTO M431 CHAMBERS FROM THE FOUNDATION STONE ('A' CLEAN, CRUSHED, ANGULAR STONE NO COMPACTION REQUIRED. 3, 357, 4, 467, 5, 56, 57 LAYER) TO THE 'C' LAYER ABOVE. FOUNDATION STONE: FILL BELOW CHAMBERS AASHTO M431 PLATE COMPACT OR ROLL TO ACHIEVE A FLAT FROM THE SUBGRADE UP TO THE FOOT (BOTTOM) CLEAN, CRUSHED, ANGULAR STONE 3, 357, 4, 467, 5, 56, 57 SURFACE. 23 OF THE CHAMBER. 1. THE LISTED AASHTO DESIGNATIONS ARE FOR GRADATIONS ONLY. THE STONE MUST ALSO BE CLEAN, CRUSHED, ANGULAR. FOR EXAMPLE, A SPECIFICATION FOR #4 STONE WOULD STATE: "CLEAN, CRUSHED, STORMTECH COMPACTION RÉQUIREMENTS ARE MET FOR 'A' LOCATION MATERIALS WHEN PLACED AND COMPACTED IN 6" (150 mm) (MAX) LIFTS USING TWO FULL COVERAGES WITH A VIBRATORY COMPACTOR. WHERE INFILTRATION SURFACES MAY BE COMPROMISED BY COMPACTION, FOR STANDARD DESIGN LOAD CONDITIONS, A FLAT SURFACE MAY BE ACHIEVED BY RAKING OR DRAGGING WITHOUT COMPACTION EQUIPMENT. FOR SPECIAL LOAD DESIGNS, CONTACT STORMTECH FOR COMPACTION REQUIREMENTS. ADS GEOSYNTHETICS 601T NON-WOVEN GEOTEXTILE ALL AROUND PAVEMENT LAYER (DESIGNED CLEAN CRUSHED, ANGULAR STONE IN A & B LAYERS BY SITE DESIGN ENGINEER) PERIMETER STONE *TO BOTTOM OF FLEXIBLE PAVEMENT. FOR UNPAVED INSTALLATIONS WHERE RUTTING FROM VEHICLES MAY ...OCCUR, INCREASE COVER TO 24" (600 mm). 6" (150 mm) (SEE NOTE 6) `MIN 18" (2.4 m) MAX (450 mm) MIN* **EXCAVATION WALL** (CAN BE SLOPED OR VERTICAL) (405 mm) DEPTH OF STONE TO BE DETERMINED BY SITE DESIGN ENGINEER 6" (150 mm) MIN 12" (300 mm) MIN -SUBGRADE SOILS (150 mm) MIN END CAP (SEE NOTE 4) NOTES: 1. SC-310 CHAMBERS SHALL CONFORM TO THE REQUIREMENTS OF ASTM F2418 "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS", OR ASTM "STANDARD SPECIFICATION FOR POLYETHYLENE (PE) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS". 2. SC-310 CHAMBERS SHALL BE DESIGNED IN ACCORDANCE WITH ASTM F2787 "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS". 3. "ACCEPTABLE FILL MATERIALS" TABLE ABOVE PROVIDES MATERIAL LOCATIONS, DESCRIPTIONS, GRADATIONS, AND COMPACTION REQUIREMENTS FOR FOUNDATION, EMBEDMENT, AND FILL MATERIALS. 4. THE SITE DESIGN ENGINEER IS RESPONSIBLE FOR ASSESSING THE BEARING RESISTANCE (ALLOWABLE BEARING CAPACITY) OF THE SUBGRADE SOILS AND THE DEPTH OF FOUNDATION STONE WITH CONSIDERATION FOR THE RANGE OF EXPECTED SOIL MOISTURE CONDITIONS. 5. PERIMETER STONE MUST BE EXTENDED HORIZONTALLY TO THE EXCAVATION WALL FOR BOTH VERTICAL AND SLOPED EXCAVATION WALLS. 6. ONCE LAYER 'C' IS PLACED, ANY SOIL/MATERIAL CAN BE PLACED IN LAYER 'D' UP TO THE FINISHED GRADE. MOST PAVEMENT SUBBASE SOILS CAN BE USED TO REPLACE THE MATERIAL REQUIREMENTS OF LAYER 'C' OR 'D' AT THE SITE DESIGN ENGINEER'S DISCRETION. SHEET 1 OF 1

SC-310 INFILTRATION CHAMBER

SHEET




SC-160LP INFILTRATION CHAMBER



23pm	1	8/13/18	KFR	JSF	JSF	PREP ROUND 1	DRAWN BY	DESIGNED BY	CALL T
- 2:2	2	10/18/18	KFR	JSF	JSF	PREP ROUND 2	JEP/RG CHECKED BY	KFR APPROVED BY	CALL T
2019	3	12/21/18	KFR	JSF	JSF	PREP ROUND 3	JSF	JSF	NAIS DE
27,	4	01/14/19	KFR	JSF	JSF	DD PRICING SET		TE (OC)	1-800
Feb	5	02/28/19	KFR	JSF	JSF	100% PREP SET	02/28	/2019	SC
	NO.	DATE	BY	CHD.	APPR.	REVISION	JOB No.	:1800077	AS







LMC	MARYMO	OOR
RE	DMOND, W	A

Appendix C

1. MGS Flood Reports

This Page Intentionally Left Blank

Program Version: MGSFlood 4.46 Program License Number: 200410007 Project Simulation Performed on: 12/17/2018 5:46 PM Report Generation Date: 12/17/2018 5:46 PM

Report Generation Date: 12/17/2018 5:46 PM			
Input File Name: 2018-12-21 Onsite Infil Project Name: LMC Marymoor Analysis Title: Onsite Infiltration Comments: PRECIPIT			
Computational Time Step (Minutes): 5			
Extended Precipitation Time Series Selected Climatic Region Number: 15			
Full Period of Record Available used for Routing Precipitation Station: 96004005 Pug Evaporation Station: 961040 Puget Evaporation Scale Factor: 0.750	et East 40 in_	5min 10/01/1939-10/01 \P	1/2097
HSPF Parameter Region Number: 1 HSPF Parameter Region Name : USGS	Default		
******** Default HSPF Parameters Used (Not	Modified by U	Jser) *********	
******* WATERSHED DEFINITION	l **********	*****	
Predevelopment/Post Development Trib	utary Area Sı	ummary Predeveloped	Post Developed
Total Subbasin Area (acres) Area of Links that Include Precip/Evap (acres) Total (acres)	4.110 0.000 4.110	4.110 0.000 4.110	
SCENARIO: PREDEVELOPEI Number of Subbasins: 1	D		
Subbasin : Subbasin 1			
Area (Acres) Till Pasture 4.110			
Subbasin Total 4.110			

SCENARIO: POSTDEVELOPED Number of Subbasins: 1					
Subbasin : Subba	basin 1 Area (Acres) 0.643 3.467				
Subbasin Total	4.110				
******* LI	NK DATA **********************************				
SCENARIO: PREDEVELOPED Number of Links: 0					

Link Name: Infiltration Chamber

Link Type: Structure Downstream Link: None

Number of Links: 1

User Specified Elevation Volume Table Used

-----SCENARIO: POSTDEVELOPED

Elevation (ft)	Pond Volume (cu-
0.00	0.
42.68	113.
42.77	225.
42.85	338.
42.93	451.
43.02	563.
43.10	676.
43.18	789.
43.27	901.
43.35	1014.
43.43	1259.
43.52	1504.
43.60	1747.
43.68	1989.
43.77	2230.
43.85	2469.
43.93	2706.
44.02	2941.
44.10	3174.
44.18	3406.
44.27	3634.
44.35	3861.
44.43	4085.
44.52	4305.

44.60	4523.
44.68	4738.
44.77	4949.
44.85	5157.
44.93	5361.
45.02	5561.
45.10	5755.
45.18	5944.
45.27	6127.
45.35	6304.
45.43	6474.
45.52	6635.
45.60	6784.
45.68	6913.
45.77	7036.
45.85	7152.
45.93	7264.
46.02	7377.
46.10	7490.
46.18	7602.
46.27	7715.
46.35	7828.
46.43	7940.
46.52	8053.
46.60	8166.
46.68	8278.
46.77	8391.
46.85	8504.

Constant Infiltration Option Used Infiltration Rate (in/hr): 20.00

Riser Geometry

Riser Geometry


Riser Structure Type : Circular
Riser Diameter (in) : 24.00

Common Length (ft) : 0.000

Riser Crest Elevation : 46.70 ft

Hydraulic Structure Geometry

Number of Devices: 0



Number of Subbasins: 1 Number of Links: 1

Recharge is computed as input to PerInd Groundwater Plus Infiltration in Structures

Model Element	redeveloped Rechar Re	echarge Amoun	t (ac-ft)	
Subbasin: Subbasin 1				
Total:	7	22.348		
	st Developed Rechar Re			
Subbasin: Subbasin 1 Link: Infiltration C	78.551			
Total:		1763.88	2	
Total Predevelopmer Average Recharge P Predeveloped: 4.5	er Year, (Number o	f Years= 158)	-	ear
*********Water Qua	lity Facility Data ***	*****		
SCE	NARIO: PREDEVEL	OPED		
Number of Links: 0				
SCEI	NARIO: POSTDEVE	LOPED		
Number of Links: 1				
******* Link: Infiltrati	on Chamber			*****
Basic Wet Pond Volu Computed Large We				
Time to Infiltrate 91%	Treatment Volume,	(Hours): 2.85		
Infiltration/Filtration S Inflow Volume (ac-ft) Inflow Volume Includ Total Runoff Infiltrate Total Runoff Filtered Primary Outflow To E Secondary Outflow T Percent Treated (Infil	: 1685.33 ing PPT-Evap (ac-ft) d (ac-ft): 1685.33, (ac-ft): 0.00, 0.00 Downstream System o Downstream Syste	1: 1685.33 100.00% % (ac-ft): 0.46 em (ac-ft): 0.0		
***********Complianc	e Point Results ***	*****		
Scenario Predevelope	ed Compliance Subb	asin: Subbasin	1	

Scenario Postdeveloped Compliance Link: Infiltration Chamber

*** Point of Compliance Flow Frequency Data ***
Recurrence Interval Computed Using Gringorten Plotting Position

Predevelopment Runoff Postdevelopment Runoff Tr (Years) Discharge (cfs) Tr (Years) Discharge (cfs)					
11 (Years)	Discharge (cis)	Tr (Years) Disch	iarge (cis)		
2-Year	0.173	2-Year	4.264E-04		
5-Year	0.377	5-Year	4.301E-04		
10-Year	0.549	10-Year	4.336E-04		
25-Year	1.147	25-Year	4.377E-04		
50-Year	1.403	50-Year	4.440E-04		
100-Year	1.978	100-Year	4.529E-04		
200-Year	2.042	200-Year	4.537E-04		
** Record too	Short to Compute Peak I	Discharge for These Re	ecurrence Intervals		
	ation Performance ****	et ha Logo Than or Equ	ual to 09/):	-100.0%	PASS
	redeveloped 50%Q2 (Mu: ursion from 50%Q2 to Q2			-100.0%	PASS
	ursion from Q2 to Q50 (M	•	• ,	-79.8%	PASS
	sion from Q2 to Q50 (Mus	,		0.0%	PASS
1 Groom Exoun	51011 110111 QZ 10 Q00 (11100	1 50 1000 than 00 70j.		0.070	17100
MEETS ALL F	LOW DURATION DESIG	N CRITERIA: PASS			

**** LID Duration Performance ****

Excursion at Predeveloped 8%Q2 (Must be Less Than 0%):	-100.0%	PASS
Maximum Excursion from 8%Q2 to 50%Q2 (Must be Less Than 0%):	-100.0%	PASS

MEETS ALL LID DURATION DESIGN CRITERIA: PASS

This Page Intentionally Left Blank

Program Version: MGSFlood 4.46
Program License Number: 200410007
Project Simulation Performed on: 02/26/2019 2:36 PM
Report Generation Date: 02/26/2019 2:36 PM

Input File Name: ROW Basin 100.fld Project Name: LMC Marymoor - ROW Infiltration Analysis Title: ROW Basin 100 Comments: PRECIPITATION INPUT					
Computational Time Step (Minutes): 5					
Extended Precipitation Time Series Selected Climatic Region Number: 15					
Precipitation Station: 96004005 Puge	Full Period of Record Available used for Routing Precipitation Station: 96004005 Puget East 40 in_5min 10/01/1939-10/01/2097 Evaporation Station: 961040 Puget East 40 in MAP Evaporation Scale Factor: 0.750				
HSPF Parameter Region Number: 1 HSPF Parameter Region Name : USGS	Default				
******** Default HSPF Parameters Used (Not	Modified by User) ******	*****		
******* WATERSHED DEFINITION	******	***			
Predevelopment/Post Development Tribu	utary Area Sumn	nary	Decileration	D t	
Developed Total Subbasin Area (acres) Area of Links that Include Precip/Evap (acres) Total (acres)	0.327 0.000 0.327	0.327 0.000 0.327	Predeveloped	Post	
SCENARIO: PREDEVELOPED Number of Subbasins: 1					
Subbasin : Subbasin 1					
Area (Acres) Till Pasture 0.327	-				
Subbasin Total 0.327					

SCENARIO: POSTDEVELOPED Number of Subbasins: 1					
	Area (Acres) 0.013				
Subbasin Total	0.327				
_	.INK DATA **********************************				
	INK DATA **********************************				
Number of Links.					

Link Name: Infiltration Chamber 100

Link Type: Structure Downstream Link: None

User Specified	Elevation Volume Table Used
Elevation (ft)	Pond Volume (cu-ft)
42.60	0.
42.68	13.
42.77	27.
42.85	40.
42.93	54.
43.02	67.
43.10	81.
43.18	109.
43.27	137.
43.35	164.
43.43	191.
43.52	217.
43.60	243.
43.68	268.
43.77	293.
43.85	317.
43.93	340.
44.02	362.
44.10	382.
44.18	401.
44.27	417.
44.35	432.
44.43	446.

44.52 44.60 44.68 44.77 44.85 44.93	460. 473. 487. 500. 514. 527.				
Constant Infiltra Infiltration Rate	ation Option Used (in/hr): 20.00	b			
Riser Diameter	y Type (in) th (ft) vation	: 18.00			
Hydraulic Stru	cture Geometry				
Number of Dev	ices: 0				
******	*****FLOOD FRE	EQUENCY AND DU	JRATION STATIST	TICS******	
Number of Sub Number of Link		REDEVELOPED			
Number of Sub Number of Link	basins: 1 s: 1	OSTDEVELOPED			
****** Subb	asin: ROW Basi	n 100 *******			
Tr (yrs)	nterval Computed Flood Peak (cfs	,	Plotting Position)		
2-Year 5-Year 10-Year 25-Year 50-Year 100-Year 200-Year		========			
Frequency Stat Flood Frequer	ncy Data(cfs) nterval Computed Flood Peak (cfs	d Using Gringorten)	Plotting Position)	******	Link Inflow
2-Year 5-Year	0.148 0.194	========			

10-Year 25-Year 50-Year 100-Year 200-Year	0.238 0.307 0.373 0.466 0.510						
Stats WSEL Freque (Recurrence Tr (yrs)	Infiltration Cham ency Data(ft) Interval Compute WSEL Peak (ft	ed Using Gringor		ງ Position)		*****	Link WSEL
1.05-Year 1.11-Year 1.25-Year 2.00-Year 3.33-Year 5-Year 10-Year 25-Year 50-Year 100-Year	42.606 42.607 42.607 42.610 42.612 42.614 42.738 43.104 43.371 43.591 eundwater Rech emputed as input	arge Summary to Perlnd Grour loped Recharge Rec	************* ndwater Plu During Sin	nulation ount (ac-ft)		es	
Subbasin: Sub	basin 1	57.471					
Model Elemen		Rec			-		
Subbasin: RO' Link: Infilt	ration Chamber	1.551 143.810					
Total:			145.361				
Average Rech	elopment Recha narge Per Year, I: 0.364 ac-ft/	(Number of Yea	ars= 158)	veloped 0.920 ac-ft	/year		
*********Wa	ter Quality Facil	ity Data *******	****				
	SCENARIO: P	REDEVELOPE	D				
Number of Lin	ks: 0						

-----SCENARIO: POSTDEVELOPED Number of Links: 1 ************* Link: Infiltration Chamber 100 Basic Wet Pond Volume (91% Exceedance): 1407. cu-ft Computed Large Wet Pond Volume, 1.5*Basic Volume: 2110. cu-ft Time to Infiltrate 91% Treatment Volume, (Hours): 2.07

Infiltration/Filtration Statistics-----

Inflow Volume (ac-ft): 143.81

Inflow Volume Including PPT-Evap (ac-ft): 143.81 Total Runoff Infiltrated (ac-ft): 143.81, 100.00%

Total Runoff Filtered (ac-ft): 0.00, 0.00%

Primary Outflow To Downstream System (ac-ft): 0.00 Secondary Outflow To Downstream System (ac-ft): 0.00 Percent Treated (Infiltrated+Filtered)/Total Volume: 100.00%

************Compliance Point Results **********

Scenario Predeveloped Compliance Subbasin: Subbasin 1

Scenario Postdeveloped Compliance Link: Infiltration Chamber 100

*** Point of Compliance Flow Frequency Data ***

Recurrence Interval Computed Using Gringorten Plotting Position

Prede	velopment Runoff	Postdevelopme	ent Runoff	
Tr (Years)	Discharge (cfs)	Tr (Years) Discha	rge (cfs)	
2-Year	1.374E-02	 2-Year	0.000	
5-Year	3.003E-02	5-Year	0.000	
10-Year	4.369E-02	10-Year	0.000	
25-Year	9.122E-02	25-Year	0.000	
50-Year	0.112	50-Year	0.000	
100-Year	0.157	100-Year	0.000	
200-Year	0.162	200-Year	0.000	

^{**} Record too Short to Compute Peak Discharge for These Recurrence Intervals

**** Flow Duration Performance ****

Excursion at Predeveloped 50%Q2 (Must be Less Than or Equal to 0%):	0.0%	PASS
Maximum Excursion from 50%Q2 to Q2 (Must be Less Than or Equal to 0%):	0.0%	PASS
Maximum Excursion from Q2 to Q50 (Must be less than 10%):	0.0%	PASS
Percent Excursion from Q2 to Q50 (Must be less than 50%):	0.0%	PASS

MEETS ALL FLOW DURATION DESIGN CRITERIA: PASS

**** LID Duration Performance ****		
Excursion at Predeveloped 8%Q2 (Must be Less Than 0%):	0.0%	PASS
Maximum Excursion from 8%Q2 to 50%Q2 (Must be Less Than 0%):	0.0%	PASS
, ,		
MEETS ALL LID DURATION DESIGN CRITERIA: PASS		

Program Version: MGSFlood 4.46 Program License Number: 200410007 Project Simulation Performed on: 02/26/2019 2:43 PM Report Generation Date: 02/26/2019 2:44 PM

•					
•					
	PRECIPITA	TION INPUT —			
Computational Time Step (Minute	es): 5				
Extended Precipitation Time Seri Climatic Region Number:	ies Selected 15				
Full Period of Record Available un Precipitation Station : Evaporation Station : Evaporation Scale Factor :		East 40 in_5mir ast 40 in MAP	n 10/01/	1939-10/01/2097	
HSPF Parameter Region Number HSPF Parameter Region Name		efault			
******* Default HSPF Parame	eters Used (Not N	Modified by User)) ******	*****	

Predevelopment/Post Dev	elopment Tribut	ary Area Summ	nary		
Developed Total Subbasin Area (acres) Area of Links that Include Preci Total (acres)	p/Evap (acres)	0.183 0.000 0.183	0.183 0.000 0.183		Post
SCENARIO: PREDEVELOPED Number of Subbasins: 1					
Subbasin : Subbasin 1Are Till Pasture 0.183	a (Acres)				
Subbasin Total 0.183					

Number of Subbasins:	ARIO: POSTDEVELOPED 1
Subbasin : RC Till Grass Impervious	oW Basin 200 Area (Acres) 0.013 0.171
Subbasin Total	0.183
	.INK DATA **********************************
******* L	.INK DATA *********************
SCENA Number of Links: 1	ARIO: POSTDEVELOPED

Link Name: Infiltration Chamber 200

Link Type: Structure Downstream Link: None

User Specified Elevation Volume Table Used Elevation (ft) Pond Volume (cu-ft) 42.60 0. 42.68 8. 42.77 16. 42.85 24. 42.93 32. 43.02 40. 43.10 47. 43.18 64. 43.27 80. 43.35 96. 43.43 112. 43.52 128. 43.60 143. 43.68 158. 43.77 172. 43.85 186. 43.93 200. 44.02 213. 44.10 225. 44.18 236. 44.27 245. 44.35 254. 44.43 263.

44.52 44.60 44.68 44.77 44.85 44.93	270. 278. 286. 294. 302. 310.					
Constant Infiltra	ation Option Used (in/hr): 20.00	d				
Riser Diameter Common Lengt	/ Type (in) th (ft) vation	: 18.00 : 0.000				
Hydraulic Stru	cture Geometry					
Number of Dev	ices: 0					
******	*****FLOOD FRE	EQUENCY AND D	URATION STATIS	STICS*****	*****	
Number of Sub Number of Link		REDEVELOPED				
Number of Sub Number of Link	basins: 1	OSTDEVELOPED				
****** Subb	asin: ROW Basi	n 200 *******				
Tr (yrs)	nterval Computed Flood Peak (cfs	•	Plotting Position))		
2-Year 5-Year 10-Year 25-Year 50-Year 100-Year 200-Year	8.060E-02 0.106 0.129 0.168 0.206 0.258 0.281	========				
Frequency Stat Flood Frequer (Recurrence In Tr (yrs)	ncy Data(cfs) nterval Computed Flood Peak (cfs	d Using Gringorter))	*****	Link Inflow
2-Year 5-Year	8.060E-02 0.106	========				

10-Year 25-Year 50-Year 100-Year 200-Year							
Stats WSEL Freque (Recurrence Tr (yrs)	Infiltration Chamency Data(ft) Interval Compute WSEL Peak (ft	ed Using Gringor		g Position)	***	*****	Link WSEL
1.05-Year 1.11-Year 1.25-Year 2.00-Year 3.33-Year 5-Year 10-Year 25-Year 50-Year 100-Year	42.605 42.606 42.607 42.609 42.611 42.612 42.676 42.988 43.185 43.473	arge Summary to Perlnd Grour loped Recharge Rec	*********** ndwater Plu During Sin harge Amo	is Infiltration i nulation ount (ac-ft)			
Subbasin: Sub		32.233			•		
Total:			32.233				
Model Elemen	Total Post Deve t	loped Recharge Rec					
Subbasin: RO\ Link: Infilt	W Basin 200 ration Chamber	1.551 79.174			•		
Total:			80.725				
Average Rech	elopment Recha narge Per Year, l: 0.204 ac-ft/	(Number of Yea	rs= 158)	veloped 0.511 ac-ft/	year		
********Water Quality Facility Data *********							
	SCENARIO: P	REDEVELOPE	D				
Number of Lin	ks: 0						

-----SCENARIO: POSTDEVELOPED Number of Links: 1 ***** ****** Link: Infiltration Chamber 200 Basic Wet Pond Volume (91% Exceedance): 767. cu-ft Computed Large Wet Pond Volume, 1.5*Basic Volume: 1151. cu-ft Time to Infiltrate 91% Treatment Volume, (Hours): 1.91 Infiltration/Filtration Statistics-----Inflow Volume (ac-ft): 79.17 Inflow Volume Including PPT-Evap (ac-ft): 79.17 Total Runoff Infiltrated (ac-ft): 79.17, 100.00% Total Runoff Filtered (ac-ft): 0.00, 0.00% Primary Outflow To Downstream System (ac-ft): 0.00 Secondary Outflow To Downstream System (ac-ft): 0.00 Percent Treated (Infiltrated+Filtered)/Total Volume: 100.00%

************Compliance Point Results **********

Scenario Predeveloped Compliance Subbasin: Subbasin 1

Scenario Postdeveloped Compliance Link: Infiltration Chamber 200

*** Point of Compliance Flow Frequency Data ***

Recurrence Interval Computed Using Gringorten Plotting Position

Prede	velopment Runoff	Postdevelopme	ent Runoff	
Tr (Years)	Discharge (cfs)	Tr (Years) Discha	rge (cfs)	
2-Year	7.707E-03	2-Year	0.000	
5-Year	1.684E-02	5-Year	0.000	
10-Year	2.450E-02	10-Year	0.000	
25-Year	5.116E-02	25-Year	0.000	
50-Year	6.260E-02	50-Year	0.000	
100-Year	8.828E-02	100-Year	0.000	
200-Year	9.111E-02	200-Year	0.000	

^{**} Record too Short to Compute Peak Discharge for These Recurrence Intervals

**** Flow Duration Performance ****

Excursion at Predeveloped 50%Q2 (Must be Less Than or Equal to 0%):	0.0%	PASS
Maximum Excursion from 50%Q2 to Q2 (Must be Less Than or Equal to 0%):	0.0%	PASS
Maximum Excursion from Q2 to Q50 (Must be less than 10%):	0.0%	PASS
Percent Excursion from Q2 to Q50 (Must be less than 50%):	0.0%	PASS

MEETS ALL FLOW DURATION DESIGN CRITERIA: PASS

**** LID Duration Performance ****		
Excursion at Predeveloped 8%Q2 (Must be Less Than 0%):	0.0%	PASS
Maximum Excursion from 8%Q2 to 50%Q2 (Must be Less Than 0%):	0.0%	PASS
, ,		
MEETS ALL LID DURATION DESIGN CRITERIA: PASS		

Program Version: MGSFlood 4.46 Program License Number: 200410007

Project Simulation Performed on: 02/26/2019 2:59 PM

Report Generation Date: 02/26/2019 3:00 PM

Input File Name: ROW Basin 300.fld Project Name: LMC Marymoor - ROW Infiltration Analysis Title: **ROW Basin 300** Comments: PRECIPITATION INPUT — Computational Time Step (Minutes): **Extended Precipitation Time Series Selected** Climatic Region Number: Full Period of Record Available used for Routing Precipitation Station: 96004005 Puget East 40 in 5min 10/01/1939-10/01/2097 961040 Puget East 40 in MAP Evaporation Station : Evaporation Scale Factor : 0.750 **HSPF** Parameter Region Number: HSPF Parameter Region Name : **USGS** Default ****** Default HSPF Parameters Used (Not Modified by User) ********** Predevelopment/Post Development Tributary Area Summary Predeveloped Post Developed Total Subbasin Area (acres) 0.098 0.098 Area of Links that Include Precip/Evap (acres) 0.000 0.000 0.098 0.098 Total (acres) -----SCENARIO: PREDEVELOPED Number of Subbasins: 1 ----- Subbasin: Subbasin 1 ----------Area (Acres) ------Till Pasture 0.098 Subbasin Total 0.098

Number of Subbasins:	ARIO: PO	OSTDEVELO	PED		
Subbasin : RC					
Till Grass	Are 0.017 0.081	ea (Acres)			
Subbasin Total	0.098	- 			
******** L				*****	
Number of Links: 0	ARIO. PR	KEDEVELOF	בט		
****** L	.INK DA ⁻	TA ******	******	*****	
Number of Links: 1	ARIO: PC	STDEVELC	PED		
Link Name: Drywell 30 Link Type: Structure Downstream Link: None					
Prismatic Pond Option I Pond Floor Elevation (ft Riser Crest Elevation (ft Max Pond Elevation (ft) Storage Depth (ft) Pond Bottom Length (ft)) i))	: 40.60 : 47.00 : 5.90 : 6.2	46.50		
Pond Bottom Width (ft) Pond Side Slopes (ft/ft) Bottom Area (sq-ft) Area at Riser Crest El (s	sq-ft) (acres)	: 6.2 : L1= 0.00 : 38. : 38. : 0.001 : 227.	L2= 0.00	W1= 0.00	W2= 0.00
Area at Max Elevation	(ac-ft) (sq-ft)	: 0.005 : 38.			
Vol at Max Elevation ((acres) cu-ft) (ac-ft)	: 0.001 : 246. : 0.006			
Constant Infiltration Opt Infiltration Rate (in/hr):		i			
Riser Geometry Riser Structure Type Riser Diameter (in) Common Length (ft)		: Circular : 18.00 : 0.000			

```
Riser Crest Elevation : 46.50 ft
Hydraulic Structure Geometry
Number of Devices:
********FLOOD FREQUENCY AND DURATION STATISTICS
   -----SCENARIO: PREDEVELOPED
Number of Subbasins: 1
Number of Links: 0
-----SCENARIO: POSTDEVELOPED
Number of Subbasins: 1
Number of Links: 1
****** Subbasin: ROW Basin 300 ********
Flood Frequency Data(cfs)
(Recurrence Interval Computed Using Gringorten Plotting Position)
Tr (yrs) Flood Peak (cfs)
2-Year 3.949E-02
5-Year 5.183E-02
  10-Year 6.392E-02
  25-Year 8.268E-02
  50-Year 0.105
100-Year 0.131
  200-Year 0.141
****** Link: Drywell 300
                                                               ++++++++
                                                                         Link
Inflow Frequency Stats
Flood Frequency Data(cfs)
(Recurrence Interval Computed Using Gringorten Plotting Position)
Tr (yrs) Flood Peak (cfs)
_____
  2-Year 3.949E-02
5-Year 5.183E-02
  10-Year 6.392E-02
  25-Year 8.268E-02
  50-Year 0.105
  100-Year 0.131
  200-Year 0.141
****** Link: Drywell 300
                                                               ******
                                                                         Link
WSEL Stats
WSEL Frequency Data(ft)
(Recurrence Interval Computed Using Gringorten Plotting Position)
Tr (yrs) WSEL Peak (ft)
_____
```

1.05-Year	40.768
1.11-Year	40.819
1.25-Year	40.954
2.00-Year	41.549
3.33-Year	41.977
5-Year	42.451
10-Year	43.288
25-Year	45.144
50-Year	46.042
100-Year	46.497

**********Groundwater Recharge Summary ********* Recharge is computed as input to Perlnd Groundwater Plus Infiltration in Structures Total Predeveloped Recharge During Simulation Model Element Recharge Amount (ac-ft) Subbasin: Subbasin 1 17.224 Total: 17.224 Total Post Developed Recharge During Simulation Model Element Recharge Amount (ac-ft) Subbasin: ROW Basin 300 2.039 Link: Drywell 300 39.761 Total: 41.801 Total Predevelopment Recharge is Less than Post Developed Average Recharge Per Year, (Number of Years= 158) Predeveloped: 0.109 ac-ft/year, Post Developed: 0.265 ac-ft/year **********Water Quality Facility Data ********* -----SCENARIO: PREDEVELOPED Number of Links: 0 -----SCENARIO: POSTDEVELOPED Number of Links: 1 ****** ****** Link: Drywell 300

Basic Wet Pond Volume (91% Exceedance): 376. cu-ft

Computed Large Wet Pond Volume, 1.5*Basic Volume: 564. cu-ft

Time to Infiltrate 91% Treatment Volume, (Hours): 5.87

Infiltration/Filtration Statistics-----

Inflow Volume (ac-ft): 39.76

Inflow Volume Including PPT-Evap (ac-ft): 39.76 Total Runoff Infiltrated (ac-ft): 39.76, 100.00% Total Runoff Filtered (ac-ft): 0.00, 0.00%

Primary Outflow To Downstream System (ac-ft): 0.00 Secondary Outflow To Downstream System (ac-ft): 0.00 Percent Treated (Infiltrated+Filtered)/Total Volume: 100.00%

***********Compliance Point Results **********

Scenario Predeveloped Compliance Subbasin: Subbasin 1

Scenario Postdeveloped Compliance Link: Drywell 300

*** Point of Compliance Flow Frequency Data ***

Recurrence Interval Computed Using Gringorten Plotting Position

Prede	velopment Runoff	Postdevelopr	nent Runoff	
Tr (Years)	Discharge (cfs)	Tr (Years) Disch	narge (cfs)	
2-Year	4.118E-03	2-Year	0.000	
5-Year	9.000E-03	5-Year	0.000	
10-Year	1.309E-02	10-Year	0.000	
25-Year	2.734E-02	25-Year	0.000	
50-Year	3.345E-02	50-Year	0.000	
100-Year	4.717E-02	100-Year	1.197E-02	
200-Year	4.869E-02	200-Year	3.162E-02	

^{**} Record too Short to Compute Peak Discharge for These Recurrence Intervals

**** Flow Duration Performance ****

-100.0%	PASS
-99.6%	PASS
-20.0%	PASS
0.0%	PASS
	-99.6% -20.0%

.....

MEETS ALL FLOW DURATION DESIGN CRITERIA: PASS

**** LID Duration Performance ****

Excursion at Predeveloped 8%Q2 (Must be Less Than 0%):	-100.0%	PASS
Maximum Excursion from 8%Q2 to 50%Q2 (Must be Less Than 0%):	-100.0%	PASS

MEETS ALL LID DURATION DESIGN CRITERIA: PASS

This Page Intentionally Left Blank

Program Version: MGSFlood 4.46 Program License Number: 200410007 Project Simulation Performed on: 02/26/2019 3:09 PM Report Generation Date: 02/26/2019 3:09 PM

Input File Name: ROW Basin 400.fld Project Name: LMC Marymoor - ROW Analysis Title: ROW Basin 400 Comments: PRECIPITA		Τ		
1112011117		•		
Computational Time Step (Minutes): 5				
Extended Precipitation Time Series Selected Climatic Region Number: 15				
Full Period of Record Available used for Routing Precipitation Station: 96004005 Puge Evaporation Station: 961040 Puget Evaporation Scale Factor: 0.750	et East 40 in_		1939-10/01/2097	
HSPF Parameter Region Number: 1 HSPF Parameter Region Name : USGS I	Default			
******* Default HSPF Parameters Used (Not	Modified by I	User) ******	*****	
******* WATERSHED DEFINITION	******	*****		
Predevelopment/Post Development Tribu	ıtary Area S	ummary		
Developed			Predeveloped	Post
Total Subbasin Area (acres)	0.107	0.107		
Area of Links that Include Precip/Evap (acres)	0.000	0.000		
Total (acres)	0.107	0.107		
SCENARIO: PREDEVELOPED Number of Subbasins: 1)			
Subbasin : Subbasin 1				
Area (Acres) Till Pasture 0.107				
1111 Fasiule 0.107				
Subbasin Total 0.107				

SCENARIO: POSTDEVELOPED Number of Subbasins: 1					
Till Grass	W Basin 400 Area (Acres) 0.012 0.095				
Subbasin Total	0.107				
_	INK DATA **********************************				
******* L	INK DATA **********************************				
SCENA Number of Links: 1	RIO: POSTDEVELOPED				

Link Name: Infiltration Chamber 400

Link Type: Structure Downstream Link: None

User Specified Elevation Volume Table Used Elevation (ft) Pond Volume (cu-ft) 42.60 0. 42.68 6. 42.77 11. 42.85 17. 42.93 22. 28. 43.02 43.10 33. 43.18 45. 43.27 56. 43.35 68. 43.43 79. 43.52 90. 43.60 100. 43.68 111. 43.77 121. 43.85 130. 43.93 140. 44.02 149. 44.10 157. 44.18 165. 44.27 172. 44.35 178. 44.43 184.

44.52 44.60 44.68 44.77 44.85 44.93	189. 195. 200. 206. 211. 217.					
Constant Infiltra	ation Option Used (in/hr): 20.00	d				
Riser Diameter Common Lengt	/ Type (in) th (ft) vation	: 18.00 : 0.000				
Hydraulic Stru	cture Geometry					
Number of Dev	ices: 0					
******	*****FLOOD FRE	EQUENCY AND D	URATION STATI	STICS*****	*****	
Number of Sub Number of Link		REDEVELOPED				
Number of Sub Number of Link	basins: 1	OSTDEVELOPED				
****** Subb	asin: ROW Basi	n 400 *******				
Tr (yrs)	nterval Computed Flood Peak (cfs	•	-)		
	4.520E-02 5.925E-02 7.292E-02 9.444E-02 0.118 0.147 0.159	========				
Frequency State Flood Frequent (Recurrence In Tr (yrs)	ncy Data(cfs) nterval Computed Flood Peak (cfs	d Using Gringorter))	*****	Link Inflow
2-Year 5-Year	4.520E-02 5.925E-02	=======				

10-Year 25-Year 50-Year 100-Year 200-Year	7.292E-02 9.444E-02 0.118 0.147 0.159						
Stats WSEL Freque (Recurrence Tr (yrs)	Infiltration Chamency Data(ft) Interval Compute WSEL Peak (ft	ed Using Gringor		g Position)	,	*****	Link WSEL
1.05-Year 1.11-Year 1.25-Year 2.00-Year 3.33-Year 5-Year 10-Year 50-Year 100-Year	42.604 42.605 42.607 42.609 42.610 42.612 42.682 42.903 43.182 eundwater Rechomputed as input	arge Summary to PerInd Grour	*********** ndwater Plu	us Infiltration in	n Structure	es	
Subbasin: Sub	basin 1	18.806	5				
Total:			18.806				
Model Elemen	Total Post Devel t		During Sin charge Amo				
Subbasin: RO\ Link: Infilt	W Basin 400 ration Chamber	1.441 44.880			•		
Total:			46.321				
Average Rech	elopment Recha narge Per Year, l: 0.119 ac-ft/y	(Number of Yea	ars= 158)	veloped 0.293 ac-ft/y	year		
********* W a	ter Quality Facil	ity Data *******	****				
	SCENARIO: P	REDEVELOPE	D				
Number of Lin	ks: 0						

************Compliance Point Results **********

Scenario Predeveloped Compliance Subbasin: Subbasin 1

Scenario Postdeveloped Compliance Link: Infiltration Chamber 400

*** Point of Compliance Flow Frequency Data ***

Recurrence Interval Computed Using Gringorten Plotting Position

Prede	velopment Runoff	Postdevelopm	ent Runoff	
Tr (Years)	Discharge (cfs)	Tr (Years) Discha	arge (cfs)	
2-Year	4.496E-03	2-Year	0.000	
5-Year	9.827E-03	5-Year	0.000	
10-Year	1.430E-02	10-Year	0.000	
25-Year	2.985E-02	25-Year	0.000	
50-Year	3.653E-02	50-Year	0.000	
100-Year	5.150E-02	100-Year	0.000	
200-Year	5.316E-02	200-Year	0.000	

^{**} Record too Short to Compute Peak Discharge for These Recurrence Intervals

**** Flow Duration Performance ****

Excursion at Predeveloped 50%Q2 (Must be Less Than or Equal to 0%):	0.0%	PASS
Maximum Excursion from 50%Q2 to Q2 (Must be Less Than or Equal to 0%):	0.0%	PASS
Maximum Excursion from Q2 to Q50 (Must be less than 10%):	0.0%	PASS
Percent Excursion from Q2 to Q50 (Must be less than 50%):	0.0%	PASS

MEETS ALL FLOW DURATION DESIGN CRITERIA: PASS

**** LID Duration Performance ****		
Excursion at Predeveloped 8%Q2 (Must be Less Than 0%):	0.0%	PASS
Maximum Excursion from 8%Q2 to 50%Q2 (Must be Less Than 0%):	0.0%	PASS
, ,		
MEETS ALL LID DURATION DESIGN CRITERIA: PASS		

Program Version: MGSFlood 4.46 Program License Number: 200410007

Project Simulation Performed on: 02/26/2019 3:17 PM

Report Generation Date: 02/26/2019 3:17 PM

Input File Name: ROW Basin 500.fld Project Name: LMC Marymoor - ROW Infiltration Analysis Title: **ROW Basin 500** Comments: PRECIPITATION INPUT — Computational Time Step (Minutes): **Extended Precipitation Time Series Selected** Climatic Region Number: Full Period of Record Available used for Routing Precipitation Station: 96004005 Puget East 40 in 5min 10/01/1939-10/01/2097 961040 Puget East 40 in MAP Evaporation Station : Evaporation Scale Factor : 0.750 **HSPF** Parameter Region Number: HSPF Parameter Region Name : **USGS** Default ****** Default HSPF Parameters Used (Not Modified by User) ********** Predevelopment/Post Development Tributary Area Summary Predeveloped Post Developed Total Subbasin Area (acres) 0.038 0.038 Area of Links that Include Precip/Evap (acres) 0.000 0.000 0.038 0.038 Total (acres) -----SCENARIO: PREDEVELOPED Number of Subbasins: 1 ----- Subbasin: Subbasin 1 ----------Area (Acres) ------Till Pasture 0.038 Subbasin Total 0.038

Number of Subbasins:	ARIO: POS T 1	TDEVELO	PED		
Subbasin : RO	W Basin 50	0			
Till Grass Impervious	Area (0.010 0.028	Acres)			
Subbasin Total	0.038				
********************************L				*****	
Number of Links: 0					
******	INK DATA	*****	*****	*****	
SCENA Number of Links: 1	RIO: POST	DEVELO	PED		
Link Name: Drywell 50 Link Type: Structure Downstream Link: None					
Prismatic Pond Option Upond Floor Elevation (ft Riser Crest Elevation (ft Max Pond Elevation (ft) Storage Depth (ft) Pond Bottom Length (ft)) :) : : :	40.60 : 47.20 6.10 10.0	46.70		
Pond Bottom Width (ft) Pond Side Slopes (ft/ft) Bottom Area (sq-ft) Area at Riser Crest El (s	: L [:] sq-ft) : (acres) :	20. 20. 0.000	L2= 0.00	W1= 0.00	W2= 0.00
Volume at Riser Crest (Area at Max Elevation	(ac-ft) : (sq-ft) :	122. 0.003 20.			
	(acres) : cu-ft) : (ac-ft) :	0.000 132. 0.003			
Constant Infiltration Opt Infiltration Rate (in/hr):					
Riser Geometry Riser Structure Type Riser Diameter (in) Common Length (ft)	: 18	ircular 8.00 .000			

```
Riser Crest Elevation : 46.70 ft
Hydraulic Structure Geometry
Number of Devices:
********FLOOD FREQUENCY AND DURATION STATISTICS
   -----SCENARIO: PREDEVELOPED
Number of Subbasins: 1
Number of Links: 0
-----SCENARIO: POSTDEVELOPED
Number of Subbasins: 1
Number of Links: 1
****** Subbasin: ROW Basin 500 ********
Flood Frequency Data(cfs)
(Recurrence Interval Computed Using Gringorten Plotting Position)
Tr (yrs) Flood Peak (cfs)
2-Year 1.430E-02
5-Year 1.889E-02
  10-Year 2.282E-02
  25-Year 2.996E-02
50-Year 3.969E-02
100-Year 4.877E-02
  200-Year 5.217E-02
****** Link: Drywell 500
                                                                  ++++++++
                                                                            Link
Inflow Frequency Stats
Flood Frequency Data(cfs)
(Recurrence Interval Computed Using Gringorten Plotting Position)
Tr (yrs) Flood Peak (cfs)
_____
  2-Year 1.430E-02
5-Year 1.889E-02
  10-Year 2.282E-02
  25-Year 2.996E-02
50-Year 3.969E-02
  100-Year 4.877E-02
  200-Year 5.217E-02
****** Link: Drywell 500
                                                                  ******
                                                                            Link
WSEL Stats
WSEL Frequency Data(ft)
(Recurrence Interval Computed Using Gringorten Plotting Position)
Tr (yrs) WSEL Peak (ft)
_____
```

1.11-Year 40 1.25-Year 40 2.00-Year 40 3.33-Year 41 5-Year 41 10-Year 41 25-Year 42 50-Year 43	0.619 0.622 0.635 0.827 0.033 0.723 0.517 0.127 0.003
---	---

***********Groundwater Recharge Summary **********

	t to PerInd Grour	ndwater Plus Infiltration in Structure	s
	Total Predeveloped Recharge During Simulation Recharge Amount (ac-ft)		
Subbasin: Subbasin 1	6.679		
Total:		6.679	
Total Post Deve Model Element		During Simulation charge Amount (ac-ft)	
Subbasin: ROW Basin 500 Link: Drywell 500	1.209		
Total:	 	15.903	
Total Predevelopment Recha Average Recharge Per Year, Predeveloped: 0.042 ac-ft/ ***********Water Quality Faci	(Number of Yea year, Post Dev lity Data *******	ars= 158) veloped: 0.101 ac-ft/year *****	
Number of Links: 0	REDEVELOPE		
SCENARIO: F	POSTDEVELOP	ED	
Number of Links: 1			
****** Link: Drywell 500			******
Basic Wet Pond Volume (91% Computed Large Wet Pond V			
Time to Infiltrate 91% Treatme	ent Volume, (Hoเ	urs): 4.05	
Infiltration/Filtration Statistics-			

Inflow Volume (ac-ft): 14.69

Inflow Volume Including PPT-Evap (ac-ft): 14.69 Total Runoff Infiltrated (ac-ft): 14.69, 100.00% Total Runoff Filtered (ac-ft): 0.00, 0.00%

Primary Outflow To Downstream System (ac-ft): 0.00 Secondary Outflow To Downstream System (ac-ft): 0.00 Percent Treated (Infiltrated+Filtered)/Total Volume: 100.00%

***********Compliance Point Results **********

Scenario Predeveloped Compliance Subbasin: Subbasin 1

Scenario Postdeveloped Compliance Link: Drywell 500

*** Point of Compliance Flow Frequency Data ***

Recurrence Interval Computed Using Gringorten Plotting Position

Prede	velopment Runoff	Postdevelopme	ent Runoff	
Tr (Years)	Discharge (cfs)	Tr (Years) Discha	rge (cfs)	
2-Year	1.597E-03	2-Year	0.000	
5-Year	3.490E-03	5-Year	0.000	
10-Year	5.077E-03	10-Year	0.000	
25-Year	1.060E-02	25-Year	0.000	
50-Year	1.297E-02	50-Year	0.000	
100-Year	1.829E-02	100-Year	0.000	
200-Year	1.888E-02	200-Year	0.000	

^{**} Record too Short to Compute Peak Discharge for These Recurrence Intervals

**** Flow Duration Performance ****

Excursion at Predeveloped 50%Q2 (Must be Less Than or Equal to 0%):	0.0%	PASS
Maximum Excursion from 50%Q2 to Q2 (Must be Less Than or Equal to 0%):	0.0%	PASS
Maximum Excursion from Q2 to Q50 (Must be less than 10%):	0.0%	PASS
Percent Excursion from Q2 to Q50 (Must be less than 50%):	0.0%	PASS

.....

MEETS ALL FLOW DURATION DESIGN CRITERIA: PASS

**** LID Duration Performance ****

Excursion at Predeveloped 8%Q2 (Must be Less Tha	n 0%):	0.0%	PASS
Maximum Excursion from 8%Q2 to 50%Q2 (Must be	Less Than 0%):	0.0%	PASS

MEETS ALL LID DURATION DESIGN CRITERIA: PASS

MGS FLOOD **PROJECT REPORT**

Program Version: MGSFlood 4.46 Program License Number: 200410007 Project Simulation Performed on: 02/26/2019 3:19 PM Report Generation Date: 02/26/2019 3:19 PM

Subbasin Total

0.303

Input File Name: ROW Basin 600.fld Project Name: LMC Marymoor - ROW In ROW Basin 600 Comments: PRECIPITA		IT		
Computational Time Step (Minutes): 5				
Extended Precipitation Time Series Selected Climatic Region Number: 15				
Full Period of Record Available used for Routing Precipitation Station: 96004005 Puget Evaporation Station: 961040 Puget Evaporation Scale Factor: 0.750			1939-10/01/2097	
HSPF Parameter Region Number: 1 HSPF Parameter Region Name : USGS D)efault			
*********** Default HSPF Parameters Used (Not N	Modified by	User) ******	*****	
******* WATERSHED DEFINITION	******	*****		
Predevelopment/Post Development Tribut	tary Area S	Summary		
Developed Total Subbasin Area (acres) Area of Links that Include Precip/Evap (acres) Total (acres)	0.303 0.000 0.303	0.303 0.000 0.303	Predeveloped	Post
SCENARIO: PREDEVELOPED Number of Subbasins: 1				
Subbasin : Subbasin 1 Area (Acres) Till Pasture 0.303				

SCENARIO: POSTDEVELOPED Number of Subbasins: 1			
Till Grass Impervious	W Basin 600 Area (Acres) 0.046 0.258		
Subbasin Total	0.303		
	INK DATA **********************************		
*******	INK DATA **********************************		
SCENA Number of Links: 1	ARIO: POSTDEVELOPED		

Link Name: Infiltration Chamber 600

Link Type: Structure Downstream Link: None

User Specified	Elevation Volume Table Used
Elevation (ft)	Pond Volume (cu-ft)
40.60	0.
40.68	12.
40.77	24.
40.85	36.
40.93	47.
41.02	72.
41.10	96.
41.18	120.
41.27	143.
41.35	166.
41.43	187.
41.52	208.
41.60	228.
41.68	246.
41.77	262.
41.85	276.
41.93	289.
42.02	300.
42.10	312.
42.18	324.
42.27	336.
42.35	348.
42.43	360.

	ation Option Use (in/hr): 20.00	ed		
Riser Geometr Riser Structure Riser Diameter Common Leng Riser Crest Ele	Type (in) th (ft)			
Hydraulic Stru	ıcture Geometry	1		
Number of Dev	vices: 0			
******	*****FLOOD FR	EQUENCY AND DURATION STATISTIC	CS******	
Number of Sub Number of Link	basins: 1	PREDEVELOPED		
Number of Sub Number of Link	basins: 1	POSTDEVELOPED		
****** Subb	asin: ROW Bas	sin 600 *******		
Tr (yrs)	nterval Compute Flood Peak (cf	,		
2-Year 5-Year 10-Year 25-Year 50-Year 100-Year 200-Year	0.125 0.162 0.203 0.261 0.330	=======================================		
Frequency Star Flood Freque	ncy Data(cfs) nterval Compute Flood Peak (cf	ed Using Gringorten Plotting Position)	******	Link Inflow
2-Year 5-Year 10-Year 25-Year 50-Year 100-Year 200-Year	0.125 0.162 0.203 0.261 0.330 0.409 0.443			

****** Link: Infiltration Chamber 600 ***** Link WSEL Stats WSEL Frequency Data(ft) (Recurrence Interval Computed Using Gringorten Plotting Position) WSEL Peak (ft) Tr (yrs) 1.05-Year 40.604 1.11-Year 40.605 1.25-Year 40.605 2.00-Year 40.608 3.33-Year 40.609 5-Year 40.610 10-Year 40.695 25-Year 40.989 50-Year 41.269 100-Year 41.503 **********Groundwater Recharge Summary ********** Recharge is computed as input to Perlnd Groundwater Plus Infiltration in Structures Total Predeveloped Recharge During Simulation Model Element Recharge Amount (ac-ft) Subbasin: Subbasin 1 53.253 Total: 53.253 Total Post Developed Recharge During Simulation Model Element Recharge Amount (ac-ft) Subbasin: ROW Basin 600 5.606 Link: Infiltration Chamber 124.813 Total: 130.418 Total Predevelopment Recharge is Less than Post Developed **Average Recharge Per Year, (Number of Years= 158)** Predeveloped: 0.337 ac-ft/year, Post Developed: 0.825 ac-ft/year **********Water Quality Facility Data ********* -----SCENARIO: PREDEVELOPED Number of Links: 0 -----SCENARIO: POSTDEVELOPED Number of Links: 1 ****** Link: Infiltration Chamber 600

Basic Wet Pond Volume (91% Exceedance): 1186. cu-ft

Computed Large Wet Pond Volume, 1.5*Basic Volume: 1780. cu-ft

Time to Infiltrate 91% Treatment Volume, (Hours): 1.98

Infiltration/Filtration Statistics-----

Inflow Volume (ac-ft): 124.81

Inflow Volume Including PPT-Evap (ac-ft): 124.81 Total Runoff Infiltrated (ac-ft): 124.81, 100.00%

Total Runoff Filtered (ac-ft): 0.00, 0.00%

Primary Outflow To Downstream System (ac-ft): 0.00 Secondary Outflow To Downstream System (ac-ft): 0.00 Percent Treated (Infiltrated+Filtered)/Total Volume: 100.00%

***********Compliance Point Results **********

Scenario Predeveloped Compliance Subbasin: Subbasin 1

Scenario Postdeveloped Compliance Link: Infiltration Chamber 600

*** Point of Compliance Flow Frequency Data ***

Recurrence Interval Computed Using Gringorten Plotting Position

Prede	velopment Runoff	Postdevelopme	ent Runoff	
Tr (Years)	Discharge (cfs)	Tr (Years) Discha	rge (cfs)	
2-Year	1.273E-02	2-Year	0.000	
5-Year	2.783E-02	5-Year	0.000	
10-Year	4.048E-02	10-Year	0.000	
25-Year	8.453E-02	25-Year	0.000	
50-Year	0.103	50-Year	0.000	
100-Year	0.146	100-Year	0.000	
200-Year	0.151	200-Year	0.000	

^{**} Record too Short to Compute Peak Discharge for These Recurrence Intervals

**** Flow Duration Performance ****

Excursion at Predeveloped 50%Q2 (Must be Less Than or Equal to 0%):	0.0%	PASS
Maximum Excursion from 50%Q2 to Q2 (Must be Less Than or Equal to 0%):	0.0%	PASS
Maximum Excursion from Q2 to Q50 (Must be less than 10%):	0.0%	PASS
Percent Excursion from Q2 to Q50 (Must be less than 50%):	0.0%	PASS

.....

MEETS ALL FLOW DURATION DESIGN CRITERIA: PASS

**** LID Duration Performance ****

Excursion at Predeveloped 8%Q2 (Must be Less Than 0%):	0.0%	PASS
Maximum Excursion from 8%Q2 to 50%Q2 (Must be Less Than 0%):	0.0%	PASS

MEETS ALL LID DURATION DESIGN CRITERIA: PASS

MGS FLOOD PROJECT REPORT

Program Version: MGSFlood 4.46 Program License Number: 200410007

Project Simulation Performed on: 02/26/2019 3:21 PM

Report Generation Date: 02/26/2019 3:22 PM

Input File Name: ROW Basin 700.fld Project Name: LMC Marymoor - ROW Infiltration Analysis Title: **ROW Basin 700** Comments: - PRECIPITATION INPUT -Computational Time Step (Minutes): **Extended Precipitation Time Series Selected** Climatic Region Number: Full Period of Record Available used for Routing Precipitation Station: 96004005 Puget East 40 in 5min 10/01/1939-10/01/2097 961040 Puget East 40 in MAP Evaporation Station : Evaporation Scale Factor : 0.750 **HSPF** Parameter Region Number: HSPF Parameter Region Name : **USGS** Default ****** Default HSPF Parameters Used (Not Modified by User) ********** Predevelopment/Post Development Tributary Area Summary Predeveloped Post Developed Total Subbasin Area (acres) 0.264 0.264 Area of Links that Include Precip/Evap (acres) 0.000 0.000 0.264 0.264 Total (acres) -----SCENARIO: PREDEVELOPED Number of Subbasins: 1 ----- Subbasin: Subbasin 1 ----------Area (Acres) ------Till Pasture 0.264 Subbasin Total 0.264

SCE Number of Subbasin		STDEVELOPED
Subbasin : Till Grass Impervious		700 a (Acres)
Subbasin Total	0.264	
**************************************	ENARIO: PRE	A ************************************
*******	** LINK DAT	A ********
SCE Number of Links: 1		STDEVELOPED

Link Name: Infiltration Chamber 700

Link Type: Structure Downstream Link: None

User Specified Elevation Volume Table Used Elevation (ft) Pond Volume (cu-ft) 42.60 0. 42.68 11. 42.77 22. 42.85 33. 42.93 44. 66. 43.02 43.10 88. 43.18 110. 43.27 131. 43.35 152. 43.43 172. 43.52 191. 43.60 209. 226. 43.68 240. 43.77 43.85 253. 43.93 264. 44.02 275. 44.10 286. 44.18 297. 44.27 308. 44.35 319. 44.43 330.

	ation Option Use (in/hr): 20.00	ed		
Riser Geometr Riser Structure Riser Diameter Common Leng Riser Crest Ele	Type (in) th (ft)			
Hydraulic Stru	ıcture Geometry			
Number of Dev	vices: 0			
******	*****FLOOD FR	EQUENCY AND DURATION STA	TISTICS*********************************	
Number of Sub Number of Link	basins: 1	PREDEVELOPED		
Number of Sub Number of Link	basins: 1	POSTDEVELOPED		
****** Subb	asin: ROW Bas	sin 700 ********		
Tr (yrs)	nterval Compute Flood Peak (cf	,	on)	
2-Year	0.110 0.144 0.179 0.230 0.290	=======================================		
Frequency Star Flood Freque	ncy Data(cfs) nterval Compute Flood Peak (cf	ed Using Gringorten Plotting Positions)	******* on)	Link Inflow
2-Year 5-Year 10-Year 25-Year 50-Year 100-Year 200-Year	0.110 0.144 0.179 0.230 0.290 0.360 0.390			

***** ****** Link: Infiltration Chamber 700 Link WSEL Stats WSEL Frequency Data(ft) (Recurrence Interval Computed Using Gringorten Plotting Position) WSEL Peak (ft) Tr (yrs) 1.05-Year 42.604 1.11-Year 42.605 1.25-Year 42.605 2.00-Year 42.607 3.33-Year 42.609 5-Year 42.609 10-Year 42.669 25-Year 42.949 50-Year 43.143 100-Year 43.420 **********Groundwater Recharge Summary ********** Recharge is computed as input to Perlnd Groundwater Plus Infiltration in Structures Total Predeveloped Recharge During Simulation Model Element Recharge Amount (ac-ft) Subbasin: Subbasin 1 46.399 Total: 46.399 Total Post Developed Recharge During Simulation Model Element Recharge Amount (ac-ft) Subbasin: ROW Basin 700 4.262 Link: Infiltration Chamber 109.942 Total: 114.205 Total Predevelopment Recharge is Less than Post Developed **Average Recharge Per Year, (Number of Years= 158)** Predeveloped: 0.294 ac-ft/year, Post Developed: 0.723 ac-ft/year **********Water Quality Facility Data ********* -----SCENARIO: PREDEVELOPED Number of Links: 0 -----SCENARIO: POSTDEVELOPED Number of Links: 1 ****** Link: Infiltration Chamber 700

Basic Wet Pond Volume (91% Exceedance): 1050. cu-ft

Computed Large Wet Pond Volume, 1.5*Basic Volume: 1575. cu-ft

Time to Infiltrate 91% Treatment Volume, (Hours): 1.92

Infiltration/Filtration Statistics-----

Inflow Volume (ac-ft): 109.94

Inflow Volume Including PPT-Evap (ac-ft): 109.94 Total Runoff Infiltrated (ac-ft): 109.94, 100.00%

Total Runoff Filtered (ac-ft): 0.00, 0.00%

Primary Outflow To Downstream System (ac-ft): 0.00 Secondary Outflow To Downstream System (ac-ft): 0.00 Percent Treated (Infiltrated+Filtered)/Total Volume: 100.00%

************Compliance Point Results **********

Scenario Predeveloped Compliance Subbasin: Subbasin 1

Scenario Postdeveloped Compliance Link: Infiltration Chamber 700

*** Point of Compliance Flow Frequency Data ***

Recurrence Interval Computed Using Gringorten Plotting Position

Predevelopment Runoff		Postdevelopment Runoff		
Tr (Years)	Discharge (cfs)	Tr (Years) Discha	arge (cfs)	
2-Year	1.109E-02	2-Year	0.000	
5-Year	2.425E-02	5-Year	0.000	
10-Year	3.527E-02	10-Year	0.000	
25-Year	7.365E-02	25-Year	0.000	
50-Year	9.012E-02	50-Year	0.000	
100-Year	0.127	100-Year	0.000	
200-Year	0.131	200-Year	0.000	

^{**} Record too Short to Compute Peak Discharge for These Recurrence Intervals

**** Flow Duration Performance ****

Excursion at Predeveloped 50%Q2 (Must be Less Than or Equal to 0%):	0.0%	PASS
Maximum Excursion from 50%Q2 to Q2 (Must be Less Than or Equal to 0%):	0.0%	PASS
Maximum Excursion from Q2 to Q50 (Must be less than 10%):		PASS
Percent Excursion from Q2 to Q50 (Must be less than 50%):	0.0%	PASS

MEETS ALL FLOW DURATION DESIGN CRITERIA: PASS

**** LID Duration Performance ****

Excursion at Predeveloped 8%Q2 (Must be Less Than 0%):	0.0%	PASS
Maximum Excursion from 8%Q2 to 50%Q2 (Must be Less Than 0%):	0.0%	PASS

MEETS ALL LID DURATION DESIGN CRITERIA: PASS

Appendix D

1. Geotechnical Report

Geotechnical report as prepared by PanGeo is included with this submittal under a separate cover.